EXISTING TYPICAL SECTION ONSITE TRUCK LOT DRIVES (SEE PLANS) FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT VAR. EXPANSION TIE ANCHOR, 3/4", 2'-6" O.C. SLOPE: 1.0% SLOPE: 4.0% & VAR 1/2"/FT. **OUTSIDE TRUCK LOT** 18'' P.C.C. PAVEMENT, 10" EXPANSION TIE ANCHOR, 3/4" P.C.C. PAVEMENT. 8" GRANULAR SUB-BASE, 4" AGGREGATE GRANULAR SUB-BASE, 4" SLOPE: 1.0% BITUMINOUS SHOULDERS SHOULDERS, 10" BITUMINOUS SHOULDERS, 8" PAINT PAVEMENT COMB. CONC. CURB & GUTTER, TYPE B-9.12 P.C.C. PAVEMENT, 10" MARKING LINE, 4" CONCRETE MEDIAN SURFACE, 4" STABILIZED SUB-BASE, 4" P.C.C. SHOULDERS, 10" **NOT TO SCALE** COMB. CONC. CURB & GUTTER, TYPE B-9.12 P.C.C. SHOULDERS, 10" **3.) PROPOSED TYPICAL SECTION** * NORTHBOUND & SOUTHBOUND REST AREAS **ONSITE TRUCK LOT DRIVES (SEE PLANS)** ** NORTHBOUND REST AREA ONLY SAW CUT INCLUDED WITH PVT REM SLOPE: 1.0%

TIE BAR

PAVED SHOULDER REMOVAL

EMBANKMENT

COMBINATION CONCRETE CURB

& GUTTER, TYPE B-6.24

TYPE A. 4"

SUB-BASE GRANULAR MATERIAL,

PAVEMENT REMOVAL

AGGREGATE BASE COURSE,

TYPE A, 12" **

PAVED SHOULDER REMOVAL

TIE BAR

P.C.C. PAVEMENT, 10" **

EMBANKMENT

COMBINATION CONCRETE CURB

& GUTTER, TYPE B-9.12 *

NOT TO SCALE
SHEET 3 OF 4

TYPICAL SECTIONS
FOR TRUCK LOT
DRIVES

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT.

DRAWN BY CHECKED BY