CONTRACT NO. 70075

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-30)RA-I-2	CHAMPAIGN	119	13
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

31100300 - SUB-BASE GRANULAR MATERIAL, TY. A, 4"			
LOCATION	SQ YD	LOCATION	SQ YD
PCC BASE COURSE WIDENING, 10"		PCC BASE COURSE WIDENING, 10"	
NORTHBOUND		SOUTHBOUND	
* 140.5' RT STA. 201+52 - 146' RT STA. 202+84	122.9	* 162' LT STA. 233+64 - 150' LT STA. 234+77.7	78.2
PCC SHOULDER, 10"		PCC SHOULDER, 10"	
NORTHBOUND		SOUTHBOUND	
STA. 187+62.3 - 195+00	817.3	STA. 127+35 - 130+83	386.7
STA. 208+48.7 - 212+41.8	436.8	STA. 144+66.7 - 150+10.93	603.6
COMB. CONC. CURB & GUTTER TY B-6.24 & B-9.12		COMB. CONC. CURB & GUTTER TY B-6.24 & B-9.12	
NORTHBOUND		SOUTHBOUND	
STA. 195+00 - 199+90	169.2	STA. 134+23 - 135+18	32.5
16' LT STA. 196+04 - 28' LT STA. 200+03	130.2	STA. 135+59 - 136+74	39.4
8.7' RT. STA. 203+12.3 - 204+91	63.5	52' RT STA. 134+00 - 25' RT STA. 136+58	88.4
27' LT STA. 203+00 - 61' LT STA. 205+60	88.9	* 157.6' LT STA. 233+55.5 - 111' LT STA. 235+43.3	47.0
* 108.6' RT STA. 200+93 - 146' RT STA. 202+84	45.9	* 110' LT STA. 235+59.6 - 111' LT STA. 241+27.6	131.5
* 110' RT STA. 194+88.6 - 107' RT STA. 200+67.3	131.4	16' RT STA. 139+71 - 143+53	131.0
		STA. 139+67 - 144+66.7	178.0
PCC DRIVEWAY PAVEMENT, 10"		PCC DRIVEWAY PAVEMENT, 10"	
NORTHBOUND		SOUTHBOUND	
STA. 204+91 - 205+33	14.0	STA. 135+18 - 135+59	15.8
SUB-TOTAL	2020.1	SUB-TOTAL	1732.1
TOTAL =		3752.2	
USE =		3752.0	

35101100- AGGREGATE BASE COURSE, TY. A, 12"	
LOCATION	SQ YD
PCC PAVEMENT, 10" JOINTED	
NORTHBOUND TRUCK PARKING LOT	
(* STATIONING FROM I-57 BASELINE)	
(AREA MEASURED IN CADD)	
STA. 194+90.00 - STA. 206+27.17	6904.0
TOTAL = 6904.0	

35400500 - PORTLAND CEMENT CONCRETE BASE COURSE WIDENING, 10"	
LOCATION	SQ YD
SOUTHBOUND	
* 162' LT STA. 233+64 - 150' LT STA. 234+77.7	78.2
(* STATIONING FROM I-57 BASELINE)	
(AREA MEASURED IN CADD)	
TOTAL =	78.2
USE =	78.0

42000501 - PORTLAND CEMENT CONCRETE PVT, 10" JOINTED	
LOCATION	SQ YD
NORTHBOUND TRUCK PARKING LOT	
STA. 194+90.00 - STA. 206+27.17	6804.0
(* STATIONING FROM I-57 BASELINE)	
(AREA MEASURED IN CADD)	
TOTAL =	6804.0

48301000 - PROTECTIVE COAT	
LOCATION	SQ YD
NORTHBOUND	
STA. 187+62.3 - 195+00	817.3
STA. 208+48.7 - 212+41.8	436.8
* 140.5' RT. STA. 201+52 - 146' RT. STA. 202+84	122.9
NORTHBOUND TRUCK PARKING LOT	
STA. 194+90.00 - STA. 206+27.17	6804.0
(* STATIONING FROM I-57 BASELINE)	
(AREA MEASURED IN CADD)	
SOUTHBOUND	
STA. 127+35 - 130+83	386.7
STA. 144+66.7 - 150+10.93	603.6
* 162' LT. STA. 233+64 - 150' LT. STA. 234+77.7	78.2
TOTAL =	9249.5
USE =	9250.0

42300600 - PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 10"	
LOCATION	SQ YD
NORTHBOUND	
STA. 204+91 - 205+33	14.0
SOUTHBOUND	
STA. 135+18 - 135+59	15.8
TOTAL =	29.8
USE =	30.0

48300500 - PORTLAND CEMENT CONCRETE SHOULDER, 10"	
LOCATION	SQ YD
NORTHBOUND	
STA. 187+62.3 - 195+00	817.3
STA. 208+48.7 - 212+41.8	436.8
SOUTHBOUND	
STA. 127+35 - 130+83	386.7
STA. 144+66.7 - 150+10.93	603.6
TOTAL =	2244.4
USE =	2245.0

SHEET 2 OF 4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 12/3/2009
FILE NAME = c:\pw_work\PWIDOT\SHEREERJM\d0143776\d570075-sht-schedules.dgn
PLOT SCALE = 42.2352 ' / IN.
USER NAME = sherer-gm