

GENERAL NOTES

G.N.-100
ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G.N.-105.09A
ALL ELEVATIONS SHOWN IN THE PLANS ARE BASED ON NORTH AMERICAN VERTICAL DATUM OF 1988. (NAVD 88)

G.N.-107.31
UTILITY LINES WERE PLOTTED FROM INFORMATION FURNISHED BY THE VARIOUS UTILITY COMPANIES INVOLVED (QUALITY LEVEL C &/OR QUALITY LEVEL D) AND THE ACCURACY SHOULD BE CONSIDERED APPROXIMATE ONLY.

UTILITY COMPANIES MAY BE ADJUSTING THEIR FACILITIES DURING CONSTRUCTION. THE CONTRACTOR SHALL COOPERATE WITH THESE ORGANIZATIONS WHILE THESE ADJUSTMENTS ARE BEING PERFORMED. J.U.L.I.E. - JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS SYSTEM (800)892-0123.

G.N.-250C (SPL)
SPECIAL TEMPORARY EROSION CONTROL SEEDING IS INCLUDED IN THIS CONTRACT TO SEED NEW EARTH SHOULDERS DURING TIME PERIODS WHEN PERMANENT SEEDING IS NOT ALLOWED. SOME OR ALL OF THE TEMPORARY EROSION CONTROL SEEDING WILL BE DELETED IF IT IS POSSIBLE TO PLACE PERMANENT SEEDING ON EARTH SHOULDERS AT THE TIME OF THEIR COMPLETION.

G.N.-406
THE QUANTITIES INCLUDED IN THE PLANS FOR HOT-MIX ASPHALT RESURFACING ARE INTENDED TO GIVE THE COVERAGE SHOWN ON THE TYPICAL CROSS SECTIONS. IT IS NOT INTENDED TO INCREASE THE THICKNESS OF THE HOT-MIX ASPHALT MIXTURE IN ORDER TO USE ALL OF THE QUANTITIES INCLUDED IN THE CONTRACT.

G.N.-406.05B
ALL LEVELING BINDER OR BINDER SHALL BE GIVEN A FOG COAT OF PRIME BEFORE THE SURFACE COURSE IS PLACED WHEN DIRECTED BY THE ENGINEER.

THE FOG COAT WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER GALLON FOR BITUMINOUS MATERIAL (PRIME COAT) AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

G.N.-406H

MIXTURE USE	SURFACE COURSE, SHOULDER, LEVEL BINDER, FLEXIBLE CONNECTOR	BASE COURSE OPTION (HMA)
AC/PG	PG 64-22	PG 64-22
RAP%(MAX)	15%	25%
DESIGN AIR VOIDS	4.0% @ N DESIGN =50	4.0% @ N DESIGN =50
MIX COMPOSITION (GRADIATION MIXTURE)	IL 9.5	IL 19.0
FRICTION AGG	MIXTURE C	N/A

G.N.-631
IF THE CONTRACTOR ELECTS TO USE THE ALTERNATE MOUNTING METHOD OF THRU DRILLING THE MOUNTING HOLES FOR THE TRAFFIC BARRIER TERMINALS, TYPE 6, THE HOLES SHALL BE DRILLED USING A CORE DRILL. A HAMMER DRILL WILL NOT BE ALLOWED.

G.N.-703A
SHORT TERM PAVEMENT MARKING SHALL BE APPLIED TO THE PAVEMENT AFTER ANY OF THE FOLLOWING: COLD MILLING AND/OR PLACING BITUMINOUS MATERIALS (PRIME COAT), LEVELING BINDER (MACHINE METHOD), BINDER AND SURFACE COURSES. SHORT TERM PAVEMENT MARKING PLACED ON THE SURFACE, SHALL COINCIDE WITH THE FINAL PAVEMENT STRIPING. SHORT TERM PAVEMENT MARKING PLACED PRIOR TO THE SURFACE SHALL COINCIDE WITH THE EXISTING PAVEMENT MARKINGS. USE 4 FEET PER 40 FEET (OR 10% PER STATION).

G.N.-781
RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED IN ACCORDANCE WITH STANDARD 781001, AND THE DETAILS SHOWN IN THE PLANS. IF THERE IS ANY DISCREPANCY BETWEEN THE STANDARD AND THE DETAILS IN THE PLANS, THE DETAILS IN THE PLANS SHALL GOVERN. THE FINAL PAVEMENT MARKINGS SHALL BE IN PLACE PRIOR TO PLACING THE RAISED REFLECTIVE PAVEMENT MARKERS AND THE RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED MIDWAY IN THE 30 FOOT (9 m) SPACE BETWEEN THE DASHED CENTERLINE STRIPES (WHEN APPLICABLE).

G.N.-1004.01
COARSE AGGREGATE GRADATION CA-10 MAY BE USED WHENEVER COARSE AGGREGATE CA-6 IS SPECIFIED IN THE STANDARD SPECIFICATIONS.

G.N.-Z0038
AN ALUMINUM TABLET OF THE TYPE SHOWN ON STANDARD 667101 SHALL BE PLACED ON THE PROPOSED STRUCTURE AS DIRECTED BY THE ENGINEER. THE BENCH MARK ELEVATION WILL BE ESTABLISHED AND MARKED BY THE DEPARTMENT. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR PERMANENT BENCH MARKS.

STANDARDS

000001-05 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02 AREA OF REINFORCEMENT BARS
001006 DECIMAL OF AN INCH AND A FOOT
280001-05 TEMPORARY EROSION CONTROL SYSTEMS
420401-08 BRIDGE APPROACH PAVEMENT CONNECTOR
482011-03 HMA SHOULDER STRIPS/SHOULDERS WITH RESURFACING OR WIDENING AND RESURFACING PROJECTS
515001-03 NAME PLATE FOR BRIDGES
630001-08 STEEL PLATE BEAM GUARDRAIL
630301-05 SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
631031-08 TRAFFIC BARRIER TERMINAL, TYPE 6
635006-03 REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-02 REFLECTOR MARKER AND MOUNTING DETAILS
667101-01 PERMANENT SURVEY MARKERS
701201-03 LANE CLOSURE, 2L, 2W, DAY ONLY
701311-03 LANE CLOSURE, 2L, 2W, MOVING OPERATIONS-DAY ONLY
701321-10 LANE CLOSURE, 2L, 2W, BRIDGE REPAIR WITH BARRIER
701901-01 TRAFFIC CONTROL DEVICES
704001-06 TEMPORARY CONCRETE BARRIER
780001-02 TYPICAL PAVEMENT MARKINGS
781001-03 TYPICAL APPLICATION RAISED REFLECTIVE PAVEMENT MARKERS

601101-01 CONCRETE HEADWALL FOR PIPE DRAIN
701301-03

RATES OF APPLICATION

THE FOLLOWING FACTORS WERE USED FOR ESTIMATING PLAN QUANTITIES AND SHALL NOT BE USED FOR THE BASIS OF FINAL QUANTITIES.

HOT - MIX ASPHALT LEVEL BINDER 0.056 TON/SQ YD/IN
HOT - MIX ASPHALT SURFACE COURSE 0.056 TON/SQ YD/IN
AGGREGATE (SURFACE, BASE AND BACK FILL) 1.80 TON/CU YD

PRIME COAT FOR HOT - MIX ASPHALT:
ON PAVEMENT 0.08 GALLONS/SQ YD
FOG COAT ON NEW BINDER 0.05 GALLONS/SQ YD

AGGREGATE (PRIME COAT):
ON EXISTING PAVEMENT 0.002 TON/SQ YD
FOG COAT ON NEW BINDER 0.001 TON/SQ YD

SHEET INDEX

1	COVER SHEET
2	INDEX, HWY STDS., GENERAL NOTES
3-4	SUMMARY OF QUANTITIES
5	EXIST. & PROP. TYPICAL SECTIONS (ROADWAY)
6-7	SCHEDULES
8	ALIGNMENT, TIES AND BENCHMARKS
9	PLAN AND PROFILE SHEET
10-11	STAGE CONSTRUCTION SHEETS
12	EROSION CONTROL SHEET
13-36	STRUCTURAL SHEETS
37-44	DETAILS
45	GENERAL PLAN AND ELEVATION FROM 2007 AS-BUILT PLANS
46-55	CROSS SECTIONS

COMMITMENTS: NONE

HURST-ROSCHE ENGINEERS, INC.
HILLSBORO, ILLINOIS 62049
(217)552-3959 FAX (217)552-3212

HR
HURST-ROSCHE ENGINEERS, INC.

FILE NAME =	USER NAME = HURST-ROSCHE	DESIGNED - JJC	REVISED -
U:\198-1239-001\work\GENNOTE.dgn	GENNOTE.dgn	DRAWN - TWC	REVISED -
		CHECKED - MAR	REVISED -
		DATE - 12-16-09	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

SCALE SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
709	G05BR08R	CHAMPAIGN	55	2
				CONTRACT NO. 70427
FED. ROAD DIST. NO. 6 ILLINDISFED. AID PROJECT				