

SCHEDULES

PAVEMENT MARKING REMOVAL		
<i>US 136</i>		
Station	to Station	SQ FT
1891+00.00	to 1895+00.00	300
Total		300

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL		
<i>US 136</i>		
Station	to Station	EACH
1891+00.00	to 1895+00.00	5
Total		5

BASE COURSE (OPTION)				
<i>US 136</i>				
Station	to Station	Side	Width (ft)	SQ YD
1891+00.00	to 1892+75.05	Rt	4	77.8
1893+31.58	to 1895+45.00	Rt	4	94.9
Total				173

IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3			
<i>US 136</i>			
Station	Side	EACH	
1890+84.96	Lt	1	
1895+59.96	Lt	1	
Total			2

IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3			
<i>US 136</i>			
Station	Side	EACH	
1890+93.96	Rt	1	
1895+18.96	Rt	1	
Total			2

CHANNEL EXCAVATION		
Wildcat Slough		
Station	to Station	CU YD
19+00.00	to 21+00.00	2010.0
Total		2010

PAVEMENT REMOVAL		
<i>US 136</i>		
Station	to Station	SQ YD
1892+12.32	to 1892+69.75	164.9
1893+63.54	to 1894+18.98	159.1
Total		324

GUARDRAIL & BARRIER WALL MARKER SCHEDULE				
ROUTE	US 136		US 136	
LOCATION	EB RT SHOULDER		WB RT SHOULDER	
SPACING*	150'		150'	
NUMBER	STA	TYPE	STA	TYPE
1	1888+97.05	GRS	1897+34.25	GRS
2	1889+77.05	GRS	1896+54.25	GRS
3	1890+57.05	GRS	1895+74.25	GRS
4	1891+37.05	GRS	1894+94.25	GRS
5	1892+17.05	BWS	1894+14.25	BWS
6	1893+67.05	BWS	1892+64.25	BWS
TOTAL GR	4	S	4	S
TOTAL BW	2	S	2	S

* AFTER INITIAL 320' FROM STD 635001
& STD 635006

LEGEND

GR GUARDRAIL MARKER
BW BARRIER WALL MARKER
S SILVER COLOR

TEMPORARY RAMP		
<i>US 136</i>		
Station	SQ YD	
1891+00.00	17.8	
1892+18.32	25.0	
1894+12.98	25.0	
1895+00.00	17.8	
Total		86

HURST-ROSCHE ENGINEERS, INC.
 HILLSBORO, ILLINOIS 62049
 (217)532-3999 FAX (217)532-3212



FILE NAME =	USER NAME = keysrb	DESIGNED - JJC	REVISED -
ct:\pw\work\pwsdot\keysrb\0142584\0570427-sht-SCHEDULE.dgn		DRAWN - TWC	REVISED -
	PLOT SCALE = 10.0000 "/> <td>CHECKED - MAR</td> <td>REVISED -</td>	CHECKED - MAR	REVISED -
	PLOT DATE = 12/17/2009	DATE - 12-16-09	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
709	(105BR)BR	CHAMPAIGN	55	7
			CONTRACT NO. 70427	
FED. ROAD DIST. NO. 5 ILLINOIS FED. AID PROJECT				