

SUMMARY OF QUANTITIES

LOCATION:

FAP 315/709	SN 057-2044 (P)
MCLEAN CTY	MCLEAN CTY
63+05.44	
TO	354+72.82
744+37.60	
RURAL	RURAL
TWO LANE	TWO LANE
80% FEDERAL	80% FEDERAL
20% STATE	20% STATE
1000	Y007

CONSTRUCTION CODE:

PAY ITEM CODE	PAY ITEM	UNIT	TOTAL	QTY	QTY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	48.0	48.0	
20200100	EARTH EXCAVATION	CU YD	89.0	55.0	34.0
20400800	FURNISHED EXCAVATION	CU YD	155.0	155.0	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	262.0	192.0	70.0
20900110	POROUS GRANULAR BACKFILL	CU YD	36.0	36.0	
* 25000200	SEEDING, CLASS 2	ACRE	0.3	0.2	0.1
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	28.0	25.0	3.0
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	28.0	25.0	3.0
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	28.0	25.0	3.0
* 25100115	MULCH METHOD 2	ACRE	0.3	0.2	0.1
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	31.0	28.0	3.0
28000400	PERIMETER EROSION BARRIER	FOOT	1,150.0	990.0	160.0
28000500	INLET AND PIPE PROTECTION	EACH	9.0	9.0	
28100105	STONE RIPRAP, CLASS A3	SQ YD	25.0	25.0	
28100201	STONE RIPRAP, CLASS A1	TON	223.0	120.0	103.0
28200200	FILTER FABRIC	SQ YD	8.0	8.0	
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	GALLON	21,411.0	21,411.0	
40300600	SEAL COAT AGGREGATE	TON	582.0	582.0	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	28,510.0	28,510.0	
40600627	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N50	TON	8,934.0	8,934.0	
40600990	TEMPORARY RAMP	SQ YD	1,145.0	1,145.0	

* SPECIALTY ITEM

FILE NAME = c:\p\work\PW1001\BUCKLESJJ\0170848\	USER NAME = bucklesjj 70507-sh-t-500.dgn	DESIGNED - DRAWN - JJB	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 315	SECTION *	COUNTY McLean	TOTAL SHEETS 115	SHEET NO. 5	
PLOT SCALE = 40.0000' / 1" IN.	CHECKED -	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.	*1101.102X1R,RS-2 & 55RS-PRK LN CONTRACT NO. 70507			
PLOT DATE = 12/9/2009	DATE - 7-16-09	REVISED -	ILLINOIS FED. AID PROJECT								