

CULVERT SCHEDULE

		UNIT	QTY	CULVERT TOTALS														
				CENTER LINE STATION	EXIST. 24" RCCP	EXIST. 36" RCCP	EXIST. SN 057-8022 (8X8) RC Box	EXIST. 3x2 RC Box Culvert	EXIST. 4x2 RC Box culvert	EXISST. 24" A.D.E. CMP	EXIST. 24" RCCP	(EX. 3X2) RC Box SN 057-2044 (PROP. 2@10X3) RC Box	EXIST./PROP. 24" A.D.E. CMP	EXIST. 3x2 RC Box Culvert	SN 057-8024 (E 5X2) RC Box SN 057-8210 (P 8X3) RC Box	EXIST. 4x6 RC Box Culvert	EXIST. 3x2 RC Box Culvert	EXIST./PROP. 4x2 RC Box Culvert
				#1	#2	#3	#4	#5	#6	#7	#8	#9	#10	#11	#12	#13	#14	#15
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNITS	48.00	48.00		48.00												
20200100	EARTH EXCAVATION	CU YD	89.00	88.71			4.44	4.01			33.21			28.53 *	4.93	7.25	6.33	
20400800	FURNISHED EXCAVATION	CU YD	156.00	155.92			9.83	8.44						36.27	87.71	9.11	4.56	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	262.00	261.10			12.80	9.60			69.30			115.40		12.60	41.40	
20900110	POROUS GRANULAR BACKFILL	CU YD	36.00	36.00								36.00						
25000200	SEEDING, CLASS 2	ACRE	0.30	0.31	0.003	0.003	0.02	0.031	0.026	0.003	0.003	0.03	0.005	0.099	0.036	0.038	0.014	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	28.00	27.91	0.27	0.27	1.80	2.76	2.31	0.27	0.27	2.72	0.45	8.87	3.21	3.46	1.24	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	28.00	27.91	0.27	0.27	1.80	2.76	2.31	0.27	0.27	2.72	0.45	8.87	3.21	3.46	1.24	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	28.00	27.91	0.27	0.27	1.80	2.76	2.31	0.27	0.27	2.72	0.45	8.87	3.21	3.46	1.24	
25100115	MULCH METHOD 2	ACRE	0.30	0.31	0.003	0.003	0.020	0.031	0.026	0.003	0.003	0.03	0.005	0.099	0.036	0.038	0.014	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUNDS	31.00	31.01	0.30	0.30	2.00	3.07	2.57	0.30	0.30	3.02	0.50	9.85	3.57	3.85	1.38	
28000400	PERIMETER EROSION BARRIER	FOOT	1,150.00	1,150.00	50.00	50.00		100.00	100.00	50.00	50.00	160.00	100.00	180.00	110.00	100.00	100.00	
28000500	INLET AND PIPE PROTECTION	EACH	9.00	9.00		1.00		1.00	1.00	1.00	1.00		1.00	1.00	1.00		1.00	
28100105	STONE RIPRAP, CLASS A3	SQ YD	25.00	24.40						7.10			7.10					10.20
28100201	STONE RIPRAP, CLASS A1	TON	223.00	222.95								102.89	24.70	53.20			42.16	
28200200	FILTER FABRIC	SQ YD	8.00	7.92	1.70	3.30				1.22	1.70							
44201735	CLASS D PATCHING, TYPE 4, 7"	SQ YD	125.00	125.00							125.00							
44201771	CLASS D PATCHING, TYPE 4, 10"	SQ YD	156.00	155.60								21.70		81.90			52.00	
48203013	HOT-MIX ASPHALT SHOULDER, 4"	SQ YD	77.00	77.00							77.00							
48203042	HOT-MIX ASPHALT SHOULDERS, 11 1/4"	SQ YD	72.00	71.20				7.00	7.00			10.90		14.40	10.90	7.00	14.00	
50105220	PIPE CULVERT REMOVAL	FOOT	52.00	52.00								52.00						
50200100	STRUCTURE EXCAVATION	CUYD	331.00	330.41							197.90			132.50				