

CULVERT SCHEDULE

		UNIT	QTY	CULVERT TOTALS														
				CENTER LINE STATION	EXIST. 24" RCCP	EXIST. 36" RCCP	EXIST. SN 057-8022 (8X8) RC Box	EXIST. 3x2 RC Box Culvert	EXIST. 4x2 RC Box culvert	EXISST. 24" A.D.E. CMP	EXIST. 24" RCCP	(EX. 3X2) RC Box SN 057-2044 (PROP. 2@10X3) RC Box	EXIST./PROP. 24" A.D.E. CMP	EXIST. 3x2 RC Box Culvert	SN 057-8024 (E 5X2) RC Box SN 057-8210 (P 8X3) RC Box	EXIST. 4x6 RC Box Culvert	EXIST. 3x2 RC Box Culvert	EXIST./PROP. 4x2 RC Box Culvert
				#1	#2	#3	#4	#5	#6	#7	#8	#9	#10	#11	#12	#13	#14	#15
54001001	BOX CULVERT END SECTION, CULVERT NO.1 (3' x 2' Pre-cast)	EACH	2.00	2.00			2.00											
54001002	BOX CULVERT END SECTION, CULVERT NO.2 (4' x 2' Pre-cast)	EACH	2.00	2.00				2.00										
54001003	BOX CULVERT END SECTION, CULVERT NO.3 (10' x 3' Cast-in-Place)	EACH	2.00	2.00							2.00							
54001004	BOX CULVERT END SECTION, CULVERT NO.4 (3' x 2' Cast-in-Place)	EACH	2.00	2.00												2.00		
54001005	BOX CULVERT END SECTION, CULVERT NO.5 (4' x 2' Pre-cast)	EACH	2.00	2.00													2.00	
54001006	BOX CULVERT END SECTION, CULVERT NO.6 (8'x 3' Pre-cast)	EACH	2.00	2.00										2.00				
54020402	PRECAST CONCRETE BOX CULVERT 4' X 2' (M273)	FOOT	56.00	56.00													56.00	
54020803	PRECAST CONCRETE BOX CULVERT 8' X 3' (M273)	FOOT	50.00	50.00										50.00				
54021003	PRECAST CONCRETE BOX CULVERT 10' X 3' (M273)	FOOT	84.00	84.00							84.00							
54207159	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 24"	FOOT	47.00	47.00								47.00						
54214719	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 24"	EACH	2.00	2.00								2.00						
54248510	CONCRETE COLLAR	CUYD	1.70	1.67				0.52	0.62								0.52	
X0322946	REMOVE CONCRETE BOX CULVERT END SECTION	EACH	10.00	10.00				2.00	2.00					2.00	2.00	2.00		
X0325561	CULVERTS TO BE GROUTED	CUYD	51.00	51.00										16.00	35.00			
X0545005	BOX CULVERT REMOVAL	LSUM	1.00	1.00							0.50						0.50	
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	36.00	22.00							10.00	4.00		4.00			4.00	
Z0032470	JOINT SEALER	FOOT	29.00	28.40	6.30	9.50				6.30	6.30							
Z0038700	PERMANENT BENCHMARKS	EACH	2.00	2.00							1.00						1.00	

* DITCH WORK ONLY, THE REST IS PAID AS STRUCTURE EXCAVATION