

ROADWAY REMOVAL SCHEDULE									
STATION TO STATION	PAVEMENT REMOVAL	COMB CURB GUTTER REM	SIDEWALK REMOVAL	MEDIAN REMOVAL	GUARDRAIL REMOVAL	FENCE REMOVAL	FOUNDATION REMOVAL	CURB REMOVAL	PAVED SHLD REMOVAL
	SQ YD	FOOT	SQ FT	SQ FT	FOOT	FOOT	SQ FT	FOOT	SQ YD
EXCHANGE AVE									
10+62.50 TO 17+38.58	3978	1209	2556	373				228	
18+83.38 TO 21+80.00	3086	671	2898	580				293	
21+80.00 TO 23+00.00	1175	265	1818	264		56		129	
7TH STREET									
12+80.00 TO 16+36.00	2306	346	2043			54			
9TH STREET									
3+90.00 TO 5+60.63		145							
BOWMAN YARD ACCESS RD									
0+00.00 TO 20+13.91	203	18				194	3639		
ACCESS ROAD SPUR									
0+00.00 TO 2+80.75	302								
CSX ACCESS ROAD									
1+45.51 TO 17+87.73						383			
EXISTINGRAMP "O"	2998	1163	963		164	496			763
EXISTING8TH STREET	989	711							
EXISTINGRAMP "P"	1531	447			252				1053
I-55					644				437
TOTALS	16568	4975	10278	1217	1060	1183	3639	650	2253