



NOTE:
WCD INSTALLED ON THE EXISTING 40' METAL POLE WITH CAMERA LOWERING DEVICE. AVOID INTERRUPTION OF CAMERA LOWERING DEVICE.

LEGEND
 - - - - - EXISTING CONNECTION
 _____ PROPOSED OR MODIFIED CONNECTION

NOTES
 1. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL INCIDENTAL CABLES NECESSARY TO MAKE THE SYSTEM OPERATIONAL. RG-59 SHALL BE 100% COPPER SHIELDING. TWISTED SHIELDED CABLE SHALL BE ACCORDING TO IMSA 20-2.
 2. ALL FIBER OPTIC CABLE MUST BE TERMINATED WITH BREAKOUT KIT AND ST STYLE CONNECTOR.
 3. TMC = TRAFFIC MANAGEMENT CENTER

COMMUNICATION DIAGRAM 1 OF 3

FILE NAME = DBT-r:\00-sht-ITSdetel1.dgn	USER NAME = asantiag	DESIGNED - CS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ITS CABLE RELOCATION PSBC CABINET MP2.4, PSBC02.4A.05C(EX.), 557002.4A.11(EX.)			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - AS	REVISED -		70	DIST 8 ITS 2010-2	ST. CLAIR	236	135			
	PLOT SCALE = 20,0010' / IN.	CHECKED - LH	REVISED -		CONTRACT NO. 76C55							
	PLOT DATE = 10/7/2009	DATE - 03/15/09	REVISED -		[ILLINOIS] FED. AID PROJECT							