

GENERAL NOTES

Reinforcement bars shall conform to the requirements of ASTM A 706 Gr 60. See Special Provisions.

Reinforcement bars designated (E) shall be epoxy coated.

All construction joints shall be bonded.


Concrete Sealer shall be applied to all exposed surfaces of the concrete facing.

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	GENERAL PLAN & ELEVATION
2	GENERAL NOTES
3	SOLDIER PILE LAYOUT
4	TYPICAL SECTIONS
5	CONCRETE FACING SECTION 1
6	CONCRETE FACING SECTION 2
7	CONCRETE FACING SECTION 3
8-9	BORINGS

TOTAL BILL OF MATERIAL

ITEM	UNIT	TOTAL
Stud Shear Connectors	Each	233
Geocomposite Wall Drain	Sq. Yd.	107
Structure Excavation	Cu. Yd.	366
Concrete Structures	Cu. Yd.	73.3
Concrete Sealer	Sq. Ft.	1018
Furnishing Soldier Piles (HP Section)	Foot	1351
Driving Soldier Piles	Foot	1351
Reinforcement Bars, Epoxy Coated	Pound	7460
Untreated Timber Lagging	Sq. Ft.	1792
Pipe Underdrains for Structures 4"	Foot	220
Form Liner Textured Surface	Sq. Ft.	1018



GENERAL NOTES
STRUCTURE NO. 082-W301

FILE NAME =	USER NAME = #USER#	DESIGNED - CMW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES - RETAINING WALL 082-W301	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN - TJW	REVISED -			998	82-1-IHB	ST. CLAIR	236	198	
		CHECKED - JSA	REVISED -			CONTRACT NO. 76C55					
		DATE - OCT 9, 2009	REVISED -			SCALE: N.T.S.	SHEET NO. 2 OF 9 SHEETS	STA. 62+00.00 TO STA. 64+00.00	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	