

PAVEMENT MARKING SCHEDULE																				
THERMOPLASTIC PAVEMENT MARKING																				
STATION			LINE, 4"											PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKERS					
			WHITE				YELLOW				LINE, 12"		LINE, 24"		LETTERS AND SYMBOLS		ONE WAY CRYSTAL	TWO WAY AMBER	REMOVAL	
			EDGE LINE	SKIP DASH	LANE LINE	DOUBLE CENTERLINE	BI-DI	LINE	SKIP DASH	YELLOW	WHITE	WHITE	TURN ARROWS		ONLY	SQ FT				SQ FT
FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT		
456+80	TO	461+00	840	210		840												11	11	22
461+00	TO	466+00	1000	250		1000												13	13	26
466+00	TO	471+00	1000	250		1200												13	15	28
471+00	TO	472+50	300	80		600									20			4	11	15
473+44	TO	475+10	332	80	166	332										31.2		8	4	12
475+10	TO	477+00	380	100		760												5	10	15
477+00	TO	479+28	456	120		912												6	12	18
479+28	TO	483+00	744	190		744												9	9	18
483+00	TO	487+78	956	240		956												12	12	24
487+78	TO	489+00	244	120		488												3	6	9
489+00	TO	492+89	778	200		1556												10	20	30
492+89	TO	493+50	122	20	61	122										15.6		4	2	6
493+50	TO	494+37	97	20	42	84										15.6		4	2	6
494+37	TO	498+45	816	200		1632												10	20	30
498+45	TO	499+00	110	20		110												2	2	4
499+00	TO	505+00	1200	300		1200												15	15	30
505+00	TO	509+08	816	200		816												10	10	20
509+08	TO	511+00	384	100		768												5	10	15
511+00	TO	513+00	400	100		800												5	10	15
513+00	TO	514+17	234	60	117	234									34	31.2		7	3	10
515+00	TO	516+74	348	90	174	348									34	31.2		8	4	12
516+74	TO	517+00	52	20		104												2	4	6
517+00	TO	520+64	728	180		1456												9	18	27
520+64	TO	521+71	214	60		214												2	2	4
521+71	TO	523+00	258	60		516												6	12	18
523+00	TO	524+68	336	90		672												4	8	12
524+68	TO	526+03	270	70	135	270										31.2		7	3	10
526+03	TO	527+05	202	50														3		3
527+05	TO	528+05	200	50	100	200										31.2		7	3	10
528+05	TO	528+48	86	20		86												2	1	3
524+48	TO	529+00	104	30	52	104												3	2	5
529+00	TO	529+48	96	30	48	96										15.6		3	1	4
537+91	TO	538+00	18				22									15.6				0
538+00	TO	544+00	1200	300			1500									93.6		15	30	45
544+00	TO	546+38	476	120			595									46.8		6	12	18
546+38	TO	548+22	368	90	130			184	50						30	31.2		9	5	14
549+24	TO	550+24	200	50	200	200									40	62.4		8	3	11
550+24	TO	556+00	1152				1440								55	93.6		14	28	42
556+00	TO	562+00	1200	300	60		1500									109.2		18	30	48
562+00	TO	566+20	840	210			1050									62.4		11	22	33
566+20	TO	567+00	160	60				160										2		2
567+00	TO	570+21	916	80	329			250										22		22
SUB TOTALS			20633	4820	1614	19420	6107	594	50	55	57	46	114.4	20.8				22		22
TOTALS						53238				112		204	868.4	20.8	19134.4			317	385	702

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.W. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILEL#	DRAWN -	REVISED -	9122			30-285-1	MADISON	18	6	
PLOT SCALE = #SCALE#	CHECKED -	REVISED -	CONTRACT NO. 76034							
PLOT DATE = #DATE#	DATE -	REVISED -	FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT							
SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____										