

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	QUANTITY
		FUNDING:	100% STATE
		COUNTY:	POPE
		LOCATION:	076-0001
		ROUTE:	IL 34
		CONST TYPE CODE:	SFTY-2A
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	84.3
50102400	CONCRETE REMOVAL	CU YD	8.5
50300225	CONCRETE STRUCTURES	CU YD	0.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	8.9
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1260
50800515	BAR SPLICERS	EACH	18
52000110	PREFORMED JOINT STRIP SEAL	FOOT	78
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT Posts	FOOT	25
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	25
63304385	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1	EACH	1
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100900	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316 (SPECIAL)	EACH	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70106700	TEMPORARY RUMBLE STRIP	EACH	6
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	8.8
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	400
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	476
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1500
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1

**Specialty Items*

FILE NAME =	USER NAME = gautneyrk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	----- ----- -----	S.B.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et\pwwork\PMIDOT\GAUTNEYRK\0156602\76153-sht-pln.dgn		DRAWN -	REVISED -			34	3(I-1)	POPE	17	4
PLOT SCALE = 20000 ' / IN.		CHECKED -	REVISED -							
PLOT DATE = 12/9/2009		DATE -	REVISED -		SCALE: _____	SHEET NO. ____ OF ____ SHEETS		STA. _____ TO STA. _____		CONTRACT NO. 78153
ILLINOIS FED. AID PROJECT										