

SUMMARY OF QUANTITIES

PAY ITEM #	DESCRIPTION	QUANTITY	UNIT	SP
20200100	EARTH EXCAVATION	319	CU YD	
21101625	TOPSOIL FURNISH AND PLACE, 6"	3462	SQ YD	
25000100	SEEDING, CLASS 1	0.72	ACRE	
25000400	NITROGEN FERTILIZER NUTRIENT	65	POUND	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	65	POUND	
25000600	POTASSIUM FERTILIZER NUTRIENT	65	POUND	
25100115	MULCH, METHOD 2	0.72	ACRE	
28000500	INLET AND PIPE PROTECTION	6	EACH	
28000510	INLET FILTERS	10	EACH	
35101400	AGGREGATE BASE COURSE, TYPE B	3400	TON	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	1985	SQ YD	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	24224	SQ FT	
42400800	DETECTABLE WARNINGS	262	SQ FT	
44000100	PAVEMENT REMOVAL	4106	SQ YD	
44000200	DRIVEWAY PAVEMENT REMOVAL	519	SQ YD	
44000500	COMBINATION CURB AND GUTTER REMOVAL	3596	FOOT	
44000600	SIDEWALK REMOVAL	1733	SQ FT	
50901720	BICYCLE RAILING	100	FOOT	
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	38	FOOT	
55100700	STORM SEWER REMOVAL 15"	10.5	FOOT	
59300100	CONTROLLED LOW-STRENGTH MATERIAL	136	CU YD	
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	1	EACH	
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	2	EACH	
60241800	INLETS, TYPE G-1	1	EACH	
60241900	INLETS, TYPE G-1, SPECIAL	1	EACH	*
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	1	EACH	*
60500060	REMOVING INLETS	5	EACH	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	3574	FOOT	
67100100	MOBILIZATION	1	L SUM	
70101700	TRAFFIC CONTROL AND PROTECTION	1	L SUM	*
72000100	SIGN PANEL - TYPE 1	74	SQ FT	
72400310	REMOVE SIGN PANEL - TYPE 1	74	SQ FT	
72400710	RELOCATE SIGN PANEL - TYPE 1	38.5	SQ FT	
72900110	METAL POST - TYPE A	20	EACH	
72900210	METAL POST - TYPE B	11	EACH	
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	517	FOOT	**
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	88	FOOT	**
78300100	PAVEMENT MARKING REMOVAL	116	SQ FT	
XX000856	MAILBOX REMOVAL AND RELOCATION	20	EACH	*
XX006499	INLET-MANHOLE, TYPE G-1, 5' DIAMETER	1	EACH	*
X6020065	INLETS, TYPE G-1, DOUBLE (SPECIAL)	4	EACH	*
Z0013798	CONSTRUCTION LAYOUT	1	L SUM	*
Revised 2-17-10	67000500 ENGINEER'S FIELD OFFICE, TYPE B	4	CAL MO	

* - SPECIAL PROVISION

** - SPECIALTY ITEM