

SUMMARY OF QUANTITIES				100% STATE STRUCTURES X771-2A
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	119	119
60240380	INLETS, ^{TYPE} B, WITH SALVAGED GRATE	EACH	1	1
60255500	MANHOLES TO BE ADJUSTED	EACH	4	4
60260200	INLETS TO BE ADJUSTED (SPECIAL)	EACH	1	1
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	2,012.5	2,012.5
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4
63200310	GUARDRAIL REMOVAL	FOOT	2,946	2,946
63400105	GUARD POSTS	EACH	8	8
63400205	GUARD POSTS REMOVAL	EACH	8	8
64200105	SHOULDER RUMBLE STRIP	FOOT	1680	1680
66502405	WOVEN WIRE FENCE REMOVAL ^{AND} REPLACEMENT	FOOT	246	246
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	7	7
67100100	MOBILIZATION	L SUM	1	1
70100700	TRAFFIC CONTROL AND PROTECTION, ^{STANDARD} 701406	L SUM	1	1
70100820	TRAFFIC CONTROL AND PROTECTION, 701451	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
70101900	TRAFFIC CONTROL AND PROTECTION (DETOUR 1)	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	208	208
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	142	142
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1880	1880
* 78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	5255	5255
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B -LINE 4"	FOOT	220	220
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	20	20
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	77	77
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	28	28
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	20	20
X0323583	SPEED INDICATOR SIGN	CAL DA	368	368
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	4	4
X5080600	MECHANICAL SPLICERS	EACH	36	36

* SPECIALTY ITEM

SUMMARY OF QUANTITIES				100% STATE STRUCTURES X771-2A
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	70	70
* X7800610	URETHANE PAVEMENT MARKING - LINE 4"	FOOT	2,800	2,800
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2
Z0038700	PERMANENT BENCH MARKS	EACH	1	1
Z0050000	REMOVAL AND REINSTALLATION OF EXISTING IMPACT ATTENUATORS	EACH	2	2

* SPECIALTY ITEM

FILE NAME =	USER NAME = dawsorkb	DESIGNED - MTM	REVISED -
c:\pwwork\pwwork\dawsorkb\d0176650\059875-3-4-500.dgn		DRAWN - JJS	REVISED -
	PLOT SCALE = 100.0000 "/ IN.	CHECKED - LLO	REVISED -
	PLOT DATE = 12/17/2009	DATE - JULY 2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(10-6HB-5)BR	CHAMPAIGN	63	4
CONTRACT NO. 90875			ILLINOIS FED. AID PROJECT	