

PAVEMENT MARKING SCHEDULE					
LOCATION	PAINT PAVEMENT MARKING LINE - 4"	URETHANE PAVEMENT MARKING LINE 4"	RAISED REFLECTIVE PAVEMENT MARKER	PREFORMED PLASTIC PVT.MRKNG. TYPE B, LINE 4"	SHORT TERM PAVEMENT MARKING
	FOOT	FOOT	EACH	FOOT	FOOT
I-74					
STA. 590+47.0 TO STA. 594+67.0		1680	20	220	208
COUNTY ROAD					
LT. STA. 40+97.0 TO STA. 59+91.0	1614	280			
RT. STA. 40+97.0 TO STA. 59+91.0	1614	280			
CL. STA. 40+97.0 TO STA. 59+91.0	410				
CL. STA. 40+97.0 TO STA. 51+55.0	785	280			
CL. STA. 48+84.0 TO STA. 59+91.0	832	280			
TOTAL	5255	2800	20	220	208

EARTHWORK SCHEDULE				
LOCATION	EARTH EX. (CUT)	EARTH EX. ADJ. FOR SHRINKAGE	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
STA. 40+97.0 TO STA. 49+66.0 (NORTH SIDE)	1016	762	6486	-5724
STA. 50+70.0 TO STA. 59+91.0 (SOUTH SIDE)	1483	1112	6174	-5062
I-74 MEDIAN NEAR ATTENUATORS				
STA. 591+61.75 TO STA. 592+41.75			22	-22
STA. 592+41.75 TO STA. 592+72.25			9	-9
STA. 592+72.25 TO STA. 593+52.25			22	-22
TOTAL	2499	1874	12,713	-10,839

USED 25% SHRINKAGE

ENTRANCE AND MAIL BOX TURNOUT SCHEDULE				
LOCATION	BIT. MTRL. (PRIME COAT)	AGGREGATE (PRIME COAT)	INCIDENTAL HMA SURFACING	AGG. SURF. CSE, TY B.
	GALLON	TON	TON	TON
RT. STA. 42+52.5	5	0.10	2	87
LT. STA. 58+36.0	5	0.10	2	69
RT. STA 58+34.0	22	0.10	10	49
TOTAL	32	0.30	14	205

EROSION AND SEDIMENT CONTROL SCHEDULE						
LOCATION	PERIMETER EROSION BARRIER	TEMPORARY EROSION CONTROL SEEDING	SEEDING CLASS 7	MULCH METHOD 2	TEMP. DITCH CHECK	INLET AND PIPE PROTECTION
	FOOT	POUNDS	ACRE	ACRE	FOOT	EACH
COUNTY ROAD						
LT. STA. 40+97.0 TO STA. 49+64.3	1004	100	1.0	1.0		
LT. STA. 50+74.5 TO STA. 59+91.0	1049	100	1.0	1.0		
RT. STA. 40+97.0 TO STA. 49+64.3	994	100	1.0	1.0		
RT. STA. 50+74.5 TO STA. 59+91.0	1083	100	1.0	1.0		
LT. STA. 41+00.0					12	
RT. STA. 41+00.0					12	
LT. STA. 43+00.0					12	
RT. STA. 43+00.0					12	
LT. STA. 44+00.0					12	
RT. STA 44+00.0					12	
LT. STA. 45+00.0					12	
RT. STA. 45+00.0					12	
LT. STA. 46+00.0					12	
RT. STA. 46+00.0					12	
LT. STA. 47+00.0					12	
RT. STA. 47+00.0					12	
LT. STA. 48+00.0					12	
RT. STA. 48+00.0					12	
LT. STA. 49+00.0					12	
RT. STA. 49+00.0					12	
LT. STA. 51+15.0					12	
RT. STA. 51+15.0					12	
LT. STA. 53+00.0					12	
RT. STA. 53+00.0					12	
LT. STA. 54+00.0					12	
RT. STA. 54+00.0					12	
LT. STA. 55+00.0					12	
RT. STA. 55+00.0					12	
LT. STA. 55+75.0					12	
RT. STA. 55+75.0					12	
LT. STA. 57+00.0					12	
RT. STA. 57+00.0					12	
LT. STA. 59+20.0					12	
RT. STA. 59+20.0					12	
RT. STA. 59+65.0					12	
RT. STA. 42+39.7 O.S. 26.1'						1
RT. STA. 42+77.2 O.S. 26.4'						1
LT. STA. 49+38.6 O.S. 86.4'						1
LT. STA. 49+38.9 O.S. 67.9'						1
RT. STA. 49+40.5 O.S. 65.6'						1
RT. STA. 49+45.3 O.S. 83.6'						1
RT. STA. 50+92.5 O.S. 80.5'						1
RT. STA. 50+96.3 O.S. 61.9'						1
LT. STA. 50+99.0 O.S. 87.0'						1
LT. STA. 51+00.0 O.S. 68.1'						1
LT. STA. 55+47.5 O.S. 44.0'						1
RT. STA. 55+49.8 O.S. 41.4'						1
LT. STA. 59+49.9 O.S. 21.5'						1
RT. STA. 59+49.9 O.S. 22.3'						1
I-74						
AREA INBETWEEN EB. & WB. I-74		25	0.25	0.25		
TOTAL	4130	425	4.25	4.25	372	14

FILE NAME =	USER NAME = dawsonkb	DESIGNED - MTM	REVISED -
ct:\pw\work\PWIDOT\DAWSONKB\d0176650\0510875-7-8-schedule.dgn		DRAWN - JJS	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED - LLQ	REVISED -
	PLOT DATE = 12/17/2009	DATE - JULY 2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N.T.S. SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(10-6HB-5)BR	CHAMPAIGN	63	8
ILLINOIS FED. AID PROJECT			CONTRACT NO. 90875	