STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION** PLANS FOR PROPOSED AMERICAN RECOVERY AND REINVESTMENT ACT **SCOTT COUNTY**

SECTION 09-00006-02-BR F.A.S. 605 (CH 3) OVER WOLF RUN CREEK PROJECT NO. ARA-0605(107)

JOB NUMBER C-96-200-10

INDEX OF SHEETS

SHEET NO.

DESCRIPTION

COVER SHEET 1.

GENERAL NOTES. TYPICAL SECTIONS. 2. SUMMARY OFQUANTITIES, SCHEDULES OF QUANTITIES

DETAILS

TRAFFIC CONTROL PLAN

STRUCTURE PLANS 5. -10.

REQUIRED HIGHWAY STANDARDS

000001-05 515001-03 631011-06 635006-03 635011-02 701901-01 780001-02 BLR 21-8 BLR 26-2 BLR 27-1

PROPOSED IMPROVEMENTS INCLUDE REPLACEMENT OF THE SUPERSTRUCTURE IN KIND INCLUDING NEW STEEL RAIL AND WEARING SURFACE ALONG WITH REPLACEMENT OF WINGWALL TOPS. RIPRAP PLACEMENT. TRAFFIC BARRIER TERMINAL REPLACEMENT AND MINOR RESURFACING IN THE IMMEDIATE STRUCTURE AREA.

> SECTION 09-00006-02-BR BEGINS STATION 132+72.00

3rd P.M.

SECTION 09-00006-02-BR ENDS STATION 134+02.00

EXISTING STRUCTURE 086-3000 SINGLE SPAN 27" PPC DECK BEAM SUPERSTRUCTURE W/ SINGLE ELEMENT SIDE MOUNTED STEEL RAIL & CONCRETE CLOSED ABUTMENTS, 54'-0" BK. TO BK. & 33'-0" O. TO O., NO SKEW (SUPERSTRUCTURE TO BE REMOVED)

LOCATION MAP

APPROXIMATE SCALE

NET LENGTH OF PROJECT = 130.00 FEET = 0.025 MILES DESIGN CLASSIFICATION: MAJOR-COLLECTOR (NON-URBAN) DESIGN ADT = 3.250 (2030) DESIGN SPEED = 60 MPH

Hutchison Engineering, Inc. JACKSONVILLE ILLINOIS

SIGNATURE ENGINEERS SEAL

SCOTT 605 09-00006-02-BR FED. ROAD DIST. NO. 7 | ILLINOIS | CONTRACT NO. 9 3 5 1



APPROVED Thronbe 25 **2**009 Make 75. Ca SCOTT COUNTY ENGINEER DI RICT SIX ENGINEER OF LOCAL ROADS & STREETS PASSED 2009 DISTRICT SIX ENGINEER OF CONSTRUCTION Released For Bid Based on Limited Review. DEPUTY DIRECTOR OF HIGHWAYS, REGION FOUR ENGINEER

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

UTILITY COMPANIES

SOYLAND POWER COOPERATIVE JACKSONVILLE. ILLINOIS

JACKSONVILLE, ILLINOIS

J.U.L.I.E.

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION 1-800-892-0123

OR 811

CONTRACT NO. 93519

2009