SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

	CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	903
	40600300	AGGREGATE (PRIME COAT)	TON	26
	40600990	TEMPORARY RAMP	SQ YD	326
	40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1626
	42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	934
	42400800	DETECTABLE WARNINGS	SQ FT	137
	44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	12904
	44000300	CURB REMOVAL	FOOT	22
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	93
	44000600	SIDEWALK REMOVAL	SQ FT	1040
	44003100	MEDIAN REMOVAL	SQ FT	699
	44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	5
	44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	103
	44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	173
	44213100	PAVEMENT FABRIC	SQ YD	276
	44213200	SAW CUTS	FOOT	1017
	44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	4576
	60600605	CONCRETE CURB, TYPE B	FOOT	22
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	110
	60624600	CORRUGATED MEDIAN	SQ FT	699
	67100100	MOBILIZATION	L SUM	1
	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1337
	70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	4194
	70300240	TEMPORARY PAVEMENT MARKING-LINE 6"	FOOT	576
	70300260	TEMPORARY PAVEMENT MARKING-LINE 12"	FOOT	124
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2033
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4194
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	576
*	78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	124

* SPECIALTY ITEMS

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
Z0017202	DOWEL BARS 1 1/2 "	EACH	400
Z0075310	TIE BARS 3/4 "	EACH	33

FILE NAME = $FILEL$	USER NAME = jeremy	DESIGNED - BFK	REVISED -
		DRAWN - DAN	REVISED -
	PLOT SCALE = $SCALE$	CHECKED - BFK	REVISED -
	PLOT DATE = 12/29/2009	DATE - 4/22/09	REVISED -

CITY OF VENICE
BROADWAY AVENUE

SUMMARY OF QUANTITIES

SCALE: N.T.S. | SHEET NO. 1 OF 1 SHEETS | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9097	09-00048-00-RS	MADISON	24	3

CONTRACT NO. 97417

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT