



STANDARDS

STD. NO.	DESCRIPTION
000001-05.	Standard Symbols, Abbreviations & Patterns
420001-07.	Pavement Joints
424001-05.	Curbs and Ramps for Sidewalks
606001-04.	Concrete curb & Combination curb and gutter
701006-3.	Off-Road Operations
701501-05.	Urban Lane Closure for sidewalk construction traffic control
701901-01.	Traffic Control Devices

GENERAL NOTES

- It is not expected that any underground facilities will be encountered during removal of sod prior to placing sidewalk. It is the contractor's responsibility to contact JULIE for locations of those facilities and avoid damage to those facilities located in the area to be excavated. Non-JULIE members must be contracted direct. Agencies known to have facilities within the project are as follows:

City of Jerseyville Ameren CIPS Frontier Communications	Cass Communications Grafton Telephone Company
---	--

 Field locations of Underground Facilities may be obtained by calling JULIE at 1-800-892-0123.
- The contractor shall confine his operations to the area within the established ROW.
- Area requiring dirt fill, raking and seed shall be included in the cost of placing concrete sidewalk.
- Any facilities which are the property of any Public Utility located within the limits of construction and require relocation shall be adjusted by their respective owners. The contractor shall notify and cooperate with the owners of any such facilities in their removal and rearrangement operations in order that these operations and the construction of this project may progress in a reasonable manner.
- All warning signs shall be 48" Fluorescent Orange
- Crosswalks and signage to be placed by Jerseyville Street Dept. upon completion of project. Signage and crosswalk markings will be placed according to the Manual on Uniform Traffic Control Devices.

Contract 97422
 Section 09-00034-02-SW

City of Jerseyville
 ARRA Funded Sidewalk 2009 - 2010
 East Fairgrounds Ave and June Street