

SUMMARY OF QUANTITIES

			COUNTY:	Jefferson			Hamilton
			Route:	IL 142			
			FUNDING:	80% FEDERAL 20% STATE			
			LOCATION:	RURAL			
CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	SN 041-0040	SN 041-0041	SN 041-0042	SN 033-0012
				0013	0013	0013	0013
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	261	261			
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	227	227			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	120	120			
40600990	TEMPORARY RAMP	SQ YD	12	12			
40604012	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5FG, MIX "D", N70	TON	34	34			
44004250	PAVED SHOULDER REMOVAL	SQ YD	261	261			
50102400	CONCRETE REMOVAL	CU YD	15.4	15.4			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	17.4	17.4			
50300260	BRIDGE DECK GROOVING	SQ YD	474	474			
50300300	PROTECTIVE COAT	SQ YD	546	546			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2,010	2,010			
50800515	BAR SPLICERS	EACH	24	24			
52000110	PREFORMED JOINT STRIP SEAL	FOOT	110	110			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	1	1	1	1
67100100	MOBILIZATION	L SUM	1	0.25	0.25	0.25	0.25



REVISD 2-17-2021

JEFFERSON & HAMILTON