

February 18, 2021

SUBJECT FAU Route 2626 (Arlington Heights Rd) Project STP-NHPP-K9ZC(737) Section 2020-115-RS&SW Cook County Contract No. 62L93 Item No. 150, March 5, 2021 Letting Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised pages 5-8 of the Special Provisions
- 2. Revised sheets 1, 2, 23, 65, 74, 81 & 98 of the Plans
- 3. Added sheet 64A to the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E. Bureau Chief, Design and Environment

Pre-Stage

STAGE / LOCATION	ТҮРЕ	DESCRIPTION	RESPONSIBLE AGENCY	DURATION OF TIME

Stage 1

STAGE / LOCATION	TYPE	DESCRIPTION	RESPONSIBLE AGENCY	DURATION OF TIME
Arlington Heights Rd at Golf Terrace (NE Corner)	Fiber Optic Handhole	Existing fiber optic handhole is in conflict with the proposed ADA Ramp improvements and will need to be adjusted during construction.	Ameritech	Contractor for Ameritech to adjust existing handhole. Days Total
Arlington Heights Rd at Pickwick Rd (SW Corner)	Gas Valve	Existing gas valve is in conflict with the proposed ADA Ramp improvements and will need to be adjusted during construction.	Nicor	Contractor for Nicor to adjust existing valve. Days Total
Arlington Heights Rd at Oakton St (NE Corner)	Gas Valve	Existing gas valve is in conflict with the proposed ADA Ramp improvements and will need to be adjusted during construction.	Nicor	Contractor for Nicor to adjust existing valve. Days Total
Arlington Heights Rd at Park St (SE Corner)	Gas Valve	Existing gas valve is in conflict with the proposed ADA Ramp improvements and will need to be adjusted during construction.	Nicor	Contractor for Nicor to adjust existing valve. Days Total

FAU Route 2626 (Arlington Heights Rd) Project STP-NHPP-K9ZC(737) Section 2020-115-RS&SW Cook County Contract No. 62L93

Arlington Heights Rd at Magnolia St (NE Corner)	Fiber Optic Handhole	Existing fiber optic handhole is in conflict with the proposed ADA Ramp improvements and will need to be adjusted during construction.	AT&T	Contractor for AT&T to adjust existing handhole. Days Total
Arlington Heights Rd at Olive St (SW Corner)	Two (2) Fiber Optic Lids	Two (2) existing lids are in conflict with the proposed ADA Ramp improvements and will need to be adjusted during construction.	AT&T	Contractor for AT&T to adjust two (2) existing lids. Days Total
Arlington Heights Rd at Maude Ave (NW Corner)	Fiber Optic Lid	Existing lid is in conflict with the proposed ADA Ramp improvements and will need to be adjusted during construction.	AT&T	Contractor for AT&T to adjust existing lid. Days Total
Arlington Heights Rd at Palatine Rd (SW Corner)	Guy Wire	Existing Guy Wire is in conflict with the proposed ADA Ramp improvements and will need to be relocated prior to construction	ComEd	Contractor for ComEd to relocate existing guy wire. Days Total

Stage 2

STAGE / LOCATION	TYPE	DESCRIPTION	RESPONSIBLE AGENCY	DURATION OF TIME

No conflicts to be resolved (or if there are conflicts they are to be listed as noted above)

Pre-Stage:	Days Total Installation
Stage 1:	Days Total Installation
Stage 2:	Days Total Installation

The following contact information is what was used during the preparation of the plans as provided by the Agency/Company responsible for resolution of the conflict.

Agency/Company Responsible to Resolve Conflict	Name of contact	Phone	E-mail address
AT&T Metro / AT&T TCA	Bobby Ahkter		Ba3817@att.com
AT&T-D	Janet C. Ahern		G11629@att.com

UTILITIES TO BE WATCHED AND PROTECTED

The areas of concern noted below have been identified by following the suggested staging plan included for the contract. The information provided is not a comprehensive list of all remaining utilities, but those which during coordination were identified as ones which might require the Department's contractor to take into consideration when making the determination of the means and methods that would be required to construct the proposed improvement. In some instances, the contractor will be responsible to notify the owner in advance of the work to take place so necessary staffing on the owner's part can be secured.

Pre-Stage

STAGE / LOCATION	TYPE	DESCRIPTION	OWNER

Stage 1

STAGE / LOCATION	TYPE	DESCRIPTION	OWNER

Stage 2

STAGE / LOCATION	ТҮРЕ	DESCRIPTION	OWNER

No facilities requiring extra consideration (or listed as noted above)

The following contact information is what was used during the preparation of the plans as provided by the owner of the facility.

Agency/Company Responsible to Resolve Conflict	Name of contact	Phone	E-mail address

The above represents the best information available to the Department and is included for the convenience of the bidder. The days required for conflict resolution should be considered in the bid as this information has also been factored into the timeline identified for the project when setting the completion date. The applicable portions of the Standard Specifications for Road and Bridge Construction shall apply.

Estimated duration of time provided above for the first conflicts identified will begin on the date of the executed contract regardless of the status of the utility relocations. The responsible agencies will be working toward resolving subsequent conflicts in conjunction with contractor activities in the number of days noted.

The estimated relocation duration must be part of the progress schedule submitted by the contractor. A utility kickoff meeting will be scheduled between the Department, the Department's contractor and the utility companies when necessary. The Department's contractor is responsible for contacting J.U.L.I.E. prior to all excavation work.