

Y030-1E

CODE NUMBER	DESCRIPTION	UNIT	QUANTITY
25200200	SUPPLEMENTAL WATERING	UNIT	2
25200700	SODDING, SPECIAL	SQ YD	550
42300800	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH, SPECIAL	SQ YD	20
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	500
44000600	SIDEWALK REMOVAL	SQ FT	500
67100100	MOBILIZATION	L SUM	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
80400100	ELECTRIC SERVICE INSTALLATION	EACH	2
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1
81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	200
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	2,950
81603210	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (EPR-TYPE RHW),1 1/4" DIA. POLYETHYLENE	FOOT	4,600
81603225	UNIT DUCT, 600V, 4-1C NO.4, 1/C NO.6 GROUND, (EPR-TYPE RHW),1 1/2" DIA. POLYETHYLENE	FOOT	4,800
81700120	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 6	FOOT	400
81700125	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 4	FOOT	1,600
81702170	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2/0	FOOT	850
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT 250 WATT	EACH	30

* - SPECIALTY ITEM

CODE NUMBER	DESCRIPTION	UNIT	QUANTITY
82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT 310 WATT	EACH	26
82500505	LIGHTING CONTROLLER, SPECIAL	EACH	1
82500540	LIGHTING CONTROLLER TYPE CB-RCS 100AMP - 480VOLT	EACH	1
83007400	LIGHT POLE, ALUMINUM, 35 FT. M.H., 10 FT. MAST ARM	EACH	30
83050800	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 12 FT. MAST ARM	EACH	18
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	260
83600215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	220
83800105	BREAKAWAY DEVICE, TRANSFORMER BASE, 11.5 INCH BOLT CIRCLE	EACH	30
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	11
84200600	REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE	EACH	10
87900200	DRILL EXISTING HANDHOLE	EACH	4
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1,800
X0324387	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	26
X0324599	ROD AND CLEAN EXISTING CONDUIT	FOOT	500
X8420110	REMOVE LIGHT POLE FOUNDATION, PARTIAL	EACH	10
XX003338	TEST HOLE	EACH	16
XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	48

FILE NAME = n:\p\proj\68238\design\plans\Sheets\68238_03_500.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60658
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = jvondra	DESIGNED - MLB	REVISED -
	DRAWN - MLB	REVISED -
PLOT SCALE = 1:8000 / 1" IN.	CHECKED - JMV	REVISED -
PLOT DATE = 12/29/2008	DATE - DECEMBER 2008	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**WAUKEGAN ROAD LIGHTING IMPROVEMENTS
SUMMARY OF QUANTITIES**

SCALE: N/A SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE. 348	SECTION 07-00102-00-LT	COUNTY COOK	TOTAL SHEETS 23	SHEET NO. 3
CONTRACT NO. 63099				
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				