

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAU 1694	07-00122-00-PV	COOK	55	5
ILLINOIS PROJECT M-9003 (125)				
VILLAGE SECTION				
CONTRACT NO. 63101				

SUMMARY OF QUANTITIES						
CODE	PAY ITEM	UNIT	TOTAL QUANTITY	1000-2A 75% FEDERAL 25% LOCAL	1000-2A 100% LOCAL	
~	60213800	RESTRICTED DEPTH CATCH BASINS, 4' DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	33	33	0
~	60224600	RESTRICTED DEPTH MANHOLES, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	0
~	60225400	RESTRICTED DEPTH MANHOLES, 5' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	12	12	0
~	60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	2	2	0
~	60248700	VALVE VAULTS, TYPE A, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	0	5
~	60248900	VALVE VAULTS, TYPE A, 5' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	0	1
~	60257900	MANHOLES TO BE RECONSTRUCTED	EACH	14	14	0
~	60266500	VALVE VAULTS TO BE REMOVED	EACH	2	0	2
~	60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	14	14	0
~	60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	26	26	0
~	60500050	REMOVING CATCH BASINS	EACH	22	22	0
~	60500060	REMOVING INLETS	EACH	3	3	0
~	60600605	CONCRETE CURB, TYPE B	FOOT	265	100	165
~	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	5,350	3,930	1,420
~	67100100	MOBILIZATION	L SUM	1	1	0
~	70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1	0
~	70106800	CHANGEABLE MESSAGE SIGN	CAL-MO	0.5	0.5	0
~	72000100	SIGN PANEL - TYPE 1	SQFT	185	185	0
~	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	465	465	0
*	78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQFT	10	0	10
*	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	480	140	340
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3,700	3,700	0
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	900	900	0
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	325	325	0
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	185	185	0
*	B2005720	TREE, PYRUS CALLERYANA CHANTICLEER (CHANTICLEER CALLERY PEAR), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	2	2	0
*	B2006220	TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	2	2	0
*~	K1003679	MULCH	CUYD	80	80	0
~	X0325544	PRESSURE CONNECTION 16" X 8"	EACH	1	0	1
~	XX000541	EXPLORATORY EXCAVATION	CUYD	175	175	0
~	XX000479	WATER MAIN REMOVAL, 6 INCH	FOOT	270	0	270
~	XX000836	PRESSURE TESTING AND DISINFECTION	L SUM	1	0	1
~	XX001464	SANITARY SEWERS, PVC, 6"	FOOT	435	435	0
~	XX001490	GATE VALVES, 8"	EACH	4	0	4
~	XX001672	STORM SEWERS, PVC, SDR 26, 12"	FOOT	348	348	0
~	XX002982	GATE VALVES, 6"	EACH	1	0	1
~	XX003036	STORM SEWERS, PVC, SDR 26, 10"	FOOT	883	883	0
~	XX003037	DUCTILE IRON FITTINGS AND ACCESSORIES	POUND	1,410	0	1,410
~	XX003059	DECORATIVE BRICK SIDEWALK	SQFT	3,045	2,755	290
~	XX003517	CONNECTION TO EXISTING WATER MAIN (NON-PRESSURE) 6"	EACH	4	0	4
~	XX005636	PIPE UNDERDRAINS, PERFORATED POLYVINY L CHLORIDE PIPE, 6"	FOOT	210	210	0
~	XX005758	TEMPORARY PAVEMENT	TON	25	25	0
~	XX006227	RESTRAINED JOINT, 8"	EACH	28	0	28
~	XX006228	RESTRAINED JOINT, 6"	EACH	40	0	40
~	XX006449	12" PVC COMBINED SEWER PIPE REPLACEMENT	FOOT	60	60	0
~	XX006450	15" PVC COMBINED SEWER PIPE REPLACEMENT	FOOT	15	15	0
~	XX006454	WATER SERVICE RELOCATION	EACH	27	27	0
~	XX006805	PORTLAND CEMENT CONCRETE BASE COURSE, 4" SPECIAL	SQFT	3,045	2,755	290
~	Z0001050	AGGREGATE SUBGRADE 12"	SQYD	3,300	3,300	0
~	Z0019600	DUST CONTROL WATERING	UNIT	100	100	0
~	Z0075300	TIE BARS	EACH	850	850	0
~	Z0076600	TRAINEES	HOUR	1,000	1,000	0

* DENOTES SPECIALTY ITEM
~ DENOTES THAT A SPECIAL PROVISION HAS BEEN PROVIDED

REVISION:	

HANCOCK ENGINEERING ♦ Civil Engineers ♦ Municipal Consultants
9700 Riverfront Plaza, Woodbury, Illinois 61554-2700
Phone: 815-395-4300 Fax: 815-395-1212
Established 1911

BROOKFIELD
GRAND BOULEVARD IMPROVEMENTS
SUMMARY OF QUANTITIES

SCALE: NOT TO SCALE

DRAWN BY: LEV/ECW/MK
CHECKED BY: JCG
DATE: 01-09-09

E.I.E. PROJECT NO.: 125-08-13501

Drawing file: W:\Projects\12508135 - Grand Blvd Grant to Veterans\Sum_Quantities.dwg Jan 29, 2009 - 9:35am