

CONTRACT NO. 63103

SUMMARY OF QUANTITIES

LOCATION OF WORK				STP - LAPP			
FUNDING SOURCE				WOLF ROAD 80% FED. 20% LOCAL	VILLAGE DR. 100% FED. (\$80,000 MAX.) REMAINDER LOCAL	DICKENS AVE. 100% FED. (\$80,000 MAX.) REMAINDER LOCAL	
SUMMARY OF QUANTITIES				STP	SECTION 112	SECTION 112	
CONSTRUCTION TYPE CODE							
ITEM #	ITEM	UNIT	TOTAL QUANTITIES	L23 1000	LY60 1000	LY60 1000	LY60 1000
28000510	INLET FILTERS	EACH	65	44	12		9
31101100	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	70	25	20		25
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	1080	825	80		175
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	1155	900	80		175
35800200	AGGREGATE BASE REPAIR	TON	40	0	20		20
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	700	500	100		100
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	2375	1530	455		390
40600300	AGGREGATE (PRIME COAT)	TON	47	30	9		8
40600400	MIXTURE FOR CRACKS, JOINTS AND FLANGEWAYS	TON	50	50	0		0
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	889	0	479		410
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1610	1610	0		0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	405	225	125		55
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	860	100	405		355
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1320	1320	0		0
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	75	75	0		0
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	5950	2450	1750		1750
42400400	PORTLAND CEMENT CONCRETE SIDEWALK, 7 INCH	SQ FT	2350	300	500		1550
42400800	DETECTABLE WARNINGS	SQ FT	500	330	140		30
~ 44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	23720	15300	4545		3875
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1155	900	80		175
44000600	SIDEWALK REMOVAL	SQ FT	8300	2750	2250		3300
~ 44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	885	665	120		100
44003100	MEDIAN REMOVAL	SQ FT	1000	1000	0		0
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	23720	15300	4545		3875
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	1	0	0		1
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	2	2	0		0
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	3	3	0		0
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	3	3	0		0
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	300	300	0		0
60624600	CORRUGATED MEDIAN	SQ FT	700	700	0		0
67100100	MOBILIZATION	L. SUM	1	0.6	0.2		0.2
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L. SUM	1	0.6	0.2		0.2
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L. SUM	1	0.6	0.2		0.2
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L. SUM	1	0.6	0.2		0.2
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	340	340	0		0
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3800	3800	0		0
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5270	4500	675		95
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	335	335	0		0
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	450	265	165		20
~ 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1450	1450	0		0
~ XX005809	CLASS B PATCHES, 10 INCH	SQ YD	865	865	0		0
~ XX006392	CLASS D PATCHES, 6" (SPECIAL)	SQ YD	205	0	110		95
~ XX006940	CLASS C PATCHES, 6" (SPECIAL)	SQ YD	205	0	110		95
~ *Z0013798	CONSTRUCTION LAYOUT	L. SUM	1	0.6	0.2		0.2
~ Z0018100	DRAINAGE STRUCTURE ADJUSTMENT (SPECIAL)	EACH	17	9	7		1
~ Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	57	36	12		9
~ Z0018700	DRAINAGE STRUCTURES TO BE REMOVED	EACH	1	0	0		1
Δ Z0076600	TRAINEES	HOUR	500	500	0		0

~ INDICATES SPECIAL PROVISION
 * INDICATES SPECIALTY ITEM
 Δ Y080

DATE: _____ BY: _____
 SURVEYED: _____ PLOTTED: _____
 GRADES CHECKED: _____
 B.M. NOTED: _____
 STRUCTURE NOTATIONS CHECKED: _____
 NOTE BOOK NO. _____
 DATE: _____ BY: _____
 SURVEYED: _____ PLOTTED: _____
 GRADES CHECKED: _____
 B.M. NOTED: _____
 STRUCTURE NOTATIONS CHECKED: _____
 NOTE BOOK NO. _____

CHRISTOPHER B. BURKE ENGINEERING LTD.
 9575 West Higgins Road, Suite 600
 Rosemont, Illinois 60018
 (847) 823-0500

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES CITY OF NORTHLAKE WOLF ROAD, VILLAGE DRIVE, DICKENS AVENUE SCALE N.T.S. DRAWN BY EDT DATE 12/5/2008 CHECKED BY MW
NAME	DATE	