

GENERAL NOTES

ROUTE NO.	SEC.	COUNTY	TOTAL SHEETS	SHEET NO.
FAP 611 (IL 81)	103T-2	Henry	35	5
FED ROAD DIST. NO.	ILLINOIS	PROJECT		
Contract #64C66				

Tree planting layout shall be performed by the District Landscape Architect. Mulch shall be placed 4" thick in a 5 foot diameter around the tree. The mulch shall be hardwood wood chips placed on weed barrier fabric. This work shall be included in the cost of the tree.

Right-of-way markers will be erected with the back face of the marker on the right-of-way line unless the new right-of-way line has been surveyed and pinned, in which instance the right-of-way markers will be erected 300 mm (12 inches) inside the new right-of-way line.

Work on this project will be in progress at the same time as work on IL 82 Cambridge to Frog Pond Road. Work on these projects shall be scheduled to keep interference between all the projects to a minimum. The contractors shall inform each other of progress of the projects and give fair warning to the other contractors when a problem might be encountered.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

Commonwealth Edison Co. Frontier/Citizens

CADD data will be available to Contractors and Consultants working on this project. This information will be provided upon request as MicroStation CADD files and Geopak coordinate geometry files ONLY. If data is required in other formats it will be your responsibility to make these conversions. If any discrepancy or inconsistency arises between the electronic data and the information on the hard copy, the information on the hard copy should be used. Contact the District's Project Engineer to request these files.

Temporary Shoulders which will not affect the removal and completion of the box culverts shall remain in place.

Aggregate Shoulder Type B quantities have been calculated for the entire project in the event Temporary Shoulders become damaged and unusable.

Program #5
(Arch. Size)
Enlarge
200%
Enlarge 107%