

# SCHEDULE OF QUANTITIES

**20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)**

UNIT	LOCATION	REMARK'S
10	777 + 70	75' RT
10	777 + 70	68' RT
8	777 + 34	67' RT
8	777 + 30	87' RT
<b>36</b>	<b>TOTAL</b>	

**20200100 EARTH EXCAVATION**

CU_YD	LOCATION	REMARK'S
320	775 + 80 TO 779 + 50 RT	
<b>320</b>	<b>TOTAL</b>	

**25100630 EROSION CONTROL BLANKET**

SQ_YD	LOCATION	REMARK'S
100	777 + 60 TO 779 + 10 RT	150' X 6'
<b>100</b>	<b>TOTAL</b>	

**25100900 TURF REINFORCEMENT MAT**

SQ_YD	LOCATION	REMARK'S
300	775 + 50 TO 780 + 0 RT	450' X 6'
<b>300</b>	<b>TOTAL</b>	

**28000300 TEMPORARY DITCH CHECKS**

EACH	LOCATION	REMARK'S
1	776 + 80 RT	
1	777 + 70 RT	
1	776 + 30 RT	
1	778 + 20 RT	
<b>4</b>	<b>TOTAL</b>	

**28000400 PERIMETER EROSION BARRIER**

FOOT	LOCATION	REMARK'S
242	777 + 49 TO 779 + 50 LT	
<b>242</b>	<b>TOTAL</b>	

**28000500 INLET AND PIPE PROTECTION**

EACH	LOCATION	REMARK'S
1	777 + 47 RT	END OF 6X4 CULVERT
<b>1</b>	<b>TOTAL</b>	

**28100107 STONE RIPRAP, CLASS A4**

SQ_YD	LOCATION	REMARK'S
72	777 + 40 RT	
72	778 + 19 LT	
<b>144</b>	<b>TOTAL</b>	

**28200200 FILTER FABRIC**

SQ_YD	LOCATION	REMARK'S
72	777 + 40 RT	
72	778 + 19 LT	
<b>144</b>	<b>TOTAL</b>	

**44201383 CLASS C PATCHES, TYPE III, 12 INCH**

SQ_YD	LOCATION	REMARK'S
228	777 + 40 TO 778 + 19	
<b>228</b>	<b>TOTAL</b>	

**48101200 AGGREGATE SHOULDER, TYPE B**

TON	LOCATION	REMARK'S
28	775 + 50 TO 777 + 40RT	
21	777 + 40 TO 778 + 19LT & RT	
35	778 + 19 TO 779 + 75LT & RT	
19	779 + 6 TO 779 + 75LT & RT	
<b>103</b>	<b>TOTAL</b>	

**50100100 REMOVAL OF EXISTING STRUCTURES**

EACH	LOCATION	REMARK'S
1	777 + 90	
<b>1</b>	<b>TOTAL</b>	

**51205200 TEMPORARY SHEET PILING**

SQ_FT.	LOCATION	REMARK'S
1993	777 + 40 TO 778 + 19	
<b>1993</b>	<b>TOTAL</b>	