

**INDEX OF SHEETS**

- 1. Coversheet
- 2. Index of Sheets & Commitments
- 3- 4. General Notes
- 5. Status of Utilities
- 6-12. Summary of Quantities
- 13-31. Schedule of Quantities
- 32-35. Typical Sections
- 36. Control Points
- 37-49. Existing and Removal Plans
- 50-63. Proposed Plans
- 64-69. Proposed Profiles
- 70-86. Staging & Traffic Control Plans
- 87-98. Erosion Control Plans
- 99-122. Drainage Plans
- 123-134. Intersection Plans Detail
- 135-140. Right of Way Plans
- 141-151. Pavement Joint Detail
- 152-164. Pavement Marking and Landscaping Plans
- 165-166. Pedestrian Crosswalk Details
- 167. Modular Retaining Wall System
- 168-170. PCC Sidewalk 6" Special
- 171. Inlet Special details
- 172. Undercut Detail
- 173-203. District Cadd Standards
- 204-429. Cross Sections **SHEET 213 DELETED**

**HIGHWAY STANDARDS**

280001-04	802306-02	701301-03	BLR 21-7
420001-07	602401-02	701311-03	
420101-04	602406-03	701326-03	
420106-04	602601-02	701501-05	
420111-02	602701-02	701602-04	
424001-05	604001-03	701901-01	
542301-02	604036-02	780001-02	
542401-01	606001-04	781001-03	
542601-01	606301-04	878001-07	
602301-02	667101-01	880006-01	

**DISTRICT STANDARDS**

205001-D4	423201-D4	602021-D4
280001-D4	424001-D4	602026-D4
406101-D4	424101-D4	602101-D4
406501-D4	424106-D4	604001-D4
423101-D4	440001-D4	611001-D4
423106-D4	542016-D4	660101-D4
423116-D4	602001-D4	667101-D4
423121-D4	602006-D4	780001-D4

**COMMITMENTS**

- Parcel NO. 406Y041 TE. Property Owner is to be notified 30 days before the start of any new construction along their property line. This will allow sufficient lead time for the relocation of their fence and landscaping.
- Parcel NO. 406Y021 TE. two wooden post that normally contain a sign at Sta. 163+25, 55' Rt will not be disturbed during construction.
- Parce NO. 406Y040TE. Cue Works will have ingress and egress at all times. Work on the entrances adjacent to Washington Road will be staggered to allow patrons on the property. The Temporary easement is solely for the purpose of entrance reconstruction, grading, shaping and working room. No materials or equipment shall be stored in this areas.
- The Engineer shall contact Mr. Hickman prior to working on the entrances so deliveries to Cue Works can be coordinated to minimize the effects on the business . Mr. Hickman can be contacted at (309) 694-2730 or (309) 256-0943.
- The following signs shall not be disturbed during construction:
  - Sta. 159+55, 55' RT - Palanza Restaurant
  - Sta. 161+60, 55' RT - Brick on front of Roland Manor Baptist Church
  - Sta. 168+04, 60' RT - Window World
  - Sta. 171+37, 55' LT - Ogborn Plumbing
  - Sta. 175+05, 47' LT - Advance Automotive
  - Sta. 177+70, 50' LT - Existing sign surrounded by Railroad ties
  - Sta. 177+71, 53' LT - Overhead door
  - Sta. 180+03, 55' LT - Small Engine Specialty
  - Sta. 181+60, 52' RT - Suburban Auto Body
  - Sta. 182+30, 55' RT - Butternut Bread
  - Sta. 185+28, 53' RT - Budweiser
  - Sta. 185+71, 53' RT - Budlite
  - Sta. 187+02, 54' RT - VM Associates
  - Sta. 191+66, RT - Car Wash
- The followings shall not be disturbed during construction:
  - Sta. 136+74, 64' RT - Gas Relay Station
  - Sta. 184+15, 96' LT - Existing 6' X 6' Wooden Fence Hiding a Garbage Bin
  - Sta. 187+05, RT - Flag Pole
  - Sta. 193+88 TO 194+75, RT - Decorative Fence enclosing the Guth Cemetery
- The Department of Transportation has agreed to replace one entrance along Washington Rd at the easterly location. This entrance will be shifted approximately 10' to the west of the current location. The southerly entrance along Oakdale Rd. will be replaced at the same location and width. The Department's contractor will not remove both entrance at the same time.

Prior to construction, the Department's resident engineer will contact Gaunt Construction thirty (30) days before entering onto this property. The contact number to be used is (309) 745-9494.