

SCHEDULE OF QUANTITIES

LOCATION		STORM SEWERS CLASS A TYPE 1				STORM SEWERS CLASS A TYPE 2					STORM SEWER PVC SDR				TRENCH BACKFILL
FROM STR.	TO STR.	12"	15"	18"	30"	12"	15"	21"	24"	30"	12"	15"	24"	27"	CU YD
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	
1	2					151.00									32.47
2	3						123.00								44.53
3	4						42.00								8.11
5	6	17.50													2.31
6	7	19.00													1.85
9	10	63.00													18.84
11	12					24.75									3.76
12	13	63.00													8.32
14	15												110.50		79.23
15	16										38.25				5.05
15	18					36.25									10.84
16	17	12.17													1.80
18	19	34.50													4.55
15	20								214.00						137.39
20	21					25.00									7.48
21	22					44.50									5.87
23	24										29.00				5.02
24	25	60.00													7.92
23	26					3.17									0.81
26	27A					28.50									7.92
27A	27					35.75									6.18
28	29	63.50													8.38
29	30	44.50									44.5				5.87
31	32										36.50				4.82
32	33										43.75				5.78
33	34										39.67				7.7
34	35								31.00						12.77
35	36								34.25						28.98
36	37								54.00						10.63
34	40							98.00							63.41
40	41										15.25				5.52
36	38	148.75													19.64
38	39	14.5													1.91
40	42							107.00							44.19
42	43							34.67							13.35
44	45										32.64				4.31
44	46	4.25													0.56
46	47	27.50													4.76
47	48	32.00													4.22
49	50	14.17													1.87
SUB-TOTAL =		618.34	0	0	0	348.92	165	239.67	333.25	0	279.56	0	0	110.5	648.92

FILE NAME = schedule.dgn	USER NAME = crespole	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

F.A.P. RTE. 399	SECTION 36 R-8	COUNTY TAZEWELL	TOTAL SHEETS 429	SHEET NO. 25
CONTRACT NO. 68258				

SCALE: SHEET NO. OF SHEETS STA. TO STA.

FED. ROAD DIST. NO. 4 [ILLINOIS] FED. AID PROJECT