

SCHEDULE OF QUANTITIES

EPOXY PAVEMENT MARKING-LETTERS AND SYMBOLS	
LOCATION	TURN ARROWS
STATION	SQ FT
STA. 138+41	8.8
STA. 138+81	8.8
STA. 141+40	8.8
STA. 141+80	8.8
STA. 146+37	8.8
STA. 146+77	8.8
STA. 150+43	8.8
STA. 150+83	8.8
STA. 155+34	8.8
STA. 155+74	8.8
STA. 158+64	8.8
STA. 159+04	8.8
STA. 162+60	8.8
STA. 163+00	8.8
STA. 165+60	8.8
STA. 166+00	8.8
STA. 168+85	8.8
STA. 169+25	8.8
STA. 172+80	8.8
STA. 173+20	8.8
STA. 176+51	8.8
STA. 176+91	8.8
STA. 180+30	8.8
STA. 180+70	8.8
STA. 183+29	8.8
STA. 183+69	8.8
STA. 187+30	8.8
STA. 187+70	8.8
STA. 191+46	8.8
STA. 191+86	8.8
STA. 195+31	8.8
STA. 195+71	8.8
RT STA. 191+18	8.8
RT STA. 192+18	8.8
TOTAL	299.2

EPOXY PAVEMENT MARKING-LINE 4"				
LOCATION	SOLID WHITE	SOLID YELLOW	YELLOW SKIP DASH	DOUBLE YELLOW
STATION TO STATION	FEET	FEET	FEET	FEET
RT STA. 132+00 TO RT STA. 139+00	700			
LT STA. 132+00 TO LT STA. 142+62	1082.0			
STA. 132+00 TO STA. 138+00				1700
RT STA. 193+08 TO RT STA. 195+03	212.5			
RT STA. 193+57 TO RT STA. 197+72	440.0			
STA. 138+00 TO STA. 143+50.31		1100.6	260.0	
STA. 145+45.21 TO STA. 147+55		419.6	100.0	
STA. 148+79 TO STA. 152+24		690.0	160.0	
STA. 154+50.6 TO STA. 156+60.5		420.0	100.0	
STA. 157+78 TO STA. 159+88.5		421.0	100.0	
STA. 161+92.59 TO STA. 163+55		324.8	80.0	
STA. 164+95 TO STA. 166+82		374.0	80.0	
STA. 167+96 TO STA. 170+00		408	100.0	
STA. 171+00 TO STA. 174+43.39		686.8	160.0	
STA. 175+52.86 TO STA. 177+75.2		444.7	100.0	
STA. 178+79.50 TO STA. 184+89.42		1219.8	300.0	
STA. 185+92.87 TO STA. 196+15.37		2045	500.0	
STA. 196+15.37 TO STA. 197+72		156.6		
SUB-TOTAL	2414.5	8710.9	2040.0	1700
TOTAL				14865.4

RAISED REFLECTIVE PAVEMENT MARKER		
LOCATION	ONE WAY (CRYSTAL)	TWO WAY (AMBER)
STATION TO STATION	EACH	EACH
RT STA. 138+00 TO RT STA. 147+55	13	
RT STA. 148+79 TO RT STA. 152+24	5	
RT STA. 153+24 TO RT STA. 156+60.50	5	
RT STA. 157+78 TO RT STA. 159+88.50	4	
RT STA. 160+76.85 TO RT STA. 163+55	4	
RT STA. 164+95 TO RT STA. 166+82	3	
RT STA. 167+96 TO RT STA. 170+00	3	
RT STA. 171+00 TO RT STA. 189+22	24	
RT STA. 190+22 TO RT STA. 192+40	4	
LT STA. 142+69.80 TO LT STA. 147+55	8	
LT STA. 148+79 TO LT STA. 152+24	5	
LT STA. 153+24 TO LT STA. 156+60.50	5	
LT STA. 157+78 TO LT STA. 159+88.50	4	
LT STA. 160+76.85 TO LT STA. 163+55	4	
LT STA. 164+95 TO LT STA. 166+82	3	
LT STA. 167+96 TO LT STA. 170+00	3	
LT STA. 171+00 TO LT STA. 192+55	28	
STA. 138+00 TO STA. 143+50.31		28
STA. 145+45.21 TO STA. 147+55		12
STA. 148+79 TO STA. 152+24		18
STA. 153+50.60 TO STA. 156+60.50		16
STA. 157+78 TO STA. 159+88.50		12
STA. 161+92.59 TO STA. 163+55		10
STA. 164+95 TO STA. 166+82		10
STA. 167+96 TO STA. 170+00		12
STA. 171+00 TO STA. 174+43.39		18
STA. 175+52.86 TO STA. 177+75.20		12
STA. 178+79.50 TO STA. 184+89.42		32
STA. 185+92.87 TO STA. 195+15.37		48
SUB-TOTAL	125	228
TOTAL		353

PAVEMENT MARKING GROOVING	
LOCATION	WHITE SKIP DASH
STATION TO STATION	SQ FT
E.B. STA. 139+02.11 TO STA. 147+55	123.7
E.B. STA. 148+02.11 TO STA. 152+24	50.1
E.B. STA. 153+24 TO STA. 156+60.50	48.8
E.B. STA. 157+78 TO STA. 163+55	83.7
E.B. STA. 164+95 TO STA. 166+82	159.6
E.B. STA. 167+96 TO STA. 170+00	44.1
E.B. STA. 171+00 TO STA. 194+59.39	197.1
W.B. STA. 142+69.80 TO STA. 147+55	70.4
W.B. STA. 148+79 TO STA. 152+24	50.1
W.B. STA. 153+24 TO STA. 156+60.50	48.8
W.B. STA. 157+78 TO STA. 163+55	83.7
W.B. STA. 164+95 TO STA. 166+82	27.1
W.B. STA. 167+96 TO STA. 170+00	44.1
W.B. STA. 171+00 TO STA. 192+24.32	308.0
TOTAL	1339.1

EPOXY PAVEMENT MARKING-LINE 12"		
LOCATION	WHITE	YELLOW
STATION	FEET	FEET
LT STA. 135+50 TO LT STA. 142+62	461.5	
RT STA. 135+50 TO RT STA. 139.02	160.8	
STA. 136+00 TO STA. 138+00		86.6
RT STA. 193+00 TO RT STA. 195+00	51.7	
LT STA. 193+59 TO LT STA. 196+50	206.9	
TOTAL	880.9	86.6

FILE NAME = schedule.dgn	USER NAME = crespole	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 1/80.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/11/2008	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE. 399	SECTION 36 R-8	COUNTY TAZEWELL	TOTAL SHEETS 429	SHEET NO. 28
FED. ROAD DIST. NO. 4 [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 68258	