



PROP. CURVE IL8CURV7
 PI STA. = 189+35.09
 I = 1° 53' 12" (LT)
 D = 0° 37' 44"
 R = 9,110.64'
 T = 150.02'
 L = 300.02'
 E = 1.24'
 e = _____
 T.R. = _____
 S.E. RUN = _____
 P.C. STA. = 187+85.07
 P.T. STA. = 190+85.09

PROP. CURVE IL8CURV8
 PI STA. = 192+35.12
 I = 1° 53' 12" (RT)
 D = 0° 37' 44"
 R = 9,110.64'
 T = 150.02'
 L = 300.02'
 E = 1.24'
 e = _____
 T.R. = _____
 S.E. RUN = _____
 P.C. STA. = 190+85.09
 P.T. STA. = 193+85.11

LEGEND FOR REMOVAL ITEMS

	PAVEMENT REMOVAL		CCC & G REMOVAL
	PAVED SHOULDER REMOVAL		H.M.A SURFACE REMOVAL (BUTT JOINT)
	DRIVEWAY PAVEMENT REMOVAL		PAVED DITCH REMOVAL
	CONCRETE MEDIAN REMOVAL		H.M.A SURFACE REMOVAL - VARIABLE DEPTH
	MEDIAN SURFACE REMOVAL		PIPE CULVERT REMOVAL
	BITUMINOUS CONCRETE REMOVAL		TREE REMOVAL

FILE NAME =
copy of ex1-plansht.dgn

USER NAME = crespole
 PLOT SCALE = 40,0000 / IN.
 PLOT DATE = 12/11/2008

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

EXISTING AND REMOVAL PLANS

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
399	36 R-8	TAZEWELL	429	47
CONTRACT NO. 68258				

FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT