

RUMBLE STRIP SCHEDULE

STATION	LENGTH	RUMBLE STRIP
FAP 328 (US 45)		
	(FT)	(SQ FT)
3+13.0 TO 3+31.0	18.0	234.0
3+76.0 TO 3+94.0	18.0	234.0
10+75.0 TO 11+03.0	28.0	364.0
12+02.0 TO 12+30.0	28.0	364.0
TOTALS		1196

PATCHING SCHEDULE

NORTHBOUND LANE

LOCATION MILEPOST	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)	TYPE	TIE BARS
RURAL					
0	6	13	8.7	II	
0	4	13	5.8	II	
0.1					
0.2	6	13	8.7	II	
0.2	12	13	17.3	III	
0.2	8	13	11.6	II	
0.3	6	13	8.7	II	
0.3					
0.3					
0.3	8	13	11.6	II	
0.4	8	13	11.6	II	
0.4	10	13	14.4	II	
0.4	6	13	8.7	II	
0.5	8	13	11.6	II	
0.5	6	13	8.7	II	
0.5	6	13	8.7	II	
0.5					
0.5					
0.6	6	13	8.7	II	
0.6					
0.7	14	13	20.2	III	
0.7	4	13	5.8	II	
0.7	6	13	8.7	II	
0.7	10	13	14.4	II	
0.8	12	13	17.3	III	
0.8	10	13	14.4	II	
0.8	14	13	20.2	III	
0.8	6	13	8.7	II	
0.8	6	13	8.7	II	
0.9	6	13	8.7	II	
SHEET TOTALS:			262.9		0

SOUTHBOUND LANE

LOCATION MILEPOST	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)	TYPE	TIE BARS
RURAL					
0.0	4	13	5.8	II	
0.0	6	13	8.7	II	
0.1	6	13	8.7	II	
0.2	12	13	17.3	III	
0.2	13	13	18.8	III	
0.2					
0.3	6	13	8.7	II	
0.3	9	13	13.0	II	
0.3	11	13	15.9	III	
0.4	6	13	8.7	II	
0.4	16	13	23.1	III	
0.4	25	13	36.1	IV	14
0.4	10	13	14.4	II	
0.5	14	13	20.2	III	
0.5	10	13	14.4	II	
0.5	6	13	8.7	II	
0.5	25	13	36.1	IV	14
0.5	10	13	14.4	II	
0.6	6	13	8.7	II	
0.6	6	13	8.7	II	
0.7	10	13	14.4	II	
0.7	13	13	18.8	III	
0.7	6	13	8.7	II	
0.7	12	13	17.3	III	
0.8	6	13	8.7	II	
0.8	6	13	8.7	II	
0.8	12	13	17.3	III	
0.8					
0.9	8	13	11.6	II	
SHEET TOTALS:			396		28

NORTHBOUND LANE

LOCATION MILEPOST	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)	TYPE	TIE BARS
RURAL					
0.9	8	13	11.6	II	
0.9	10	13	14.4	II	
0.9	6	13	8.7	II	
0.9	8	13	11.6	II	
0.9	6	13	8.7	II	
1	9	13	13.0	II	
1	8	13	11.6	II	
1	6	13	8.7	II	
1	8	13	11.6	II	
1	10	13	14.4	II	
1.1	10	13	14.4	II	
1.1	8	13	11.6	II	
1.1	9	13	13.0	II	
1.1	25	13	36.1	IV	14
1.2	10	13	14.4	II	
1.2	6	13	8.7	II	
1.2	10	13	14.4	II	
1.2	10	13	14.4	II	
1.3	6	13	8.7	II	
1.3	8	13	11.6	II	
1.4	4	13	5.8	II	
1.4	20	13	28.9	IV	
1.4					
1.4					
1.5	8	13	11.6	II	
1.5	8	13	11.6	II	
1.5	4	13	5.8	II	
1.5					
1.6	10	13	14.4	II	
SHEET TOTALS:			339		14

SOUTHBOUND LANE

LOCATION MILEPOST	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)	TYPE	TIE BARS
RURAL					
0.9	6	13	8.7	II	
0.9	8	13	11.6	II	
0.9	6	13	8.7	II	
0.9	8	13	11.6	II	
0.9					
1.0	8	13	11.6	II	
1.0	8	13	11.6	II	
1.0					
1.0					
1.1	10	13	14.4	II	
1.1	8	13	11.6	II	
1.1	6	13	8.7	II	
1.1					
1.2	10	13	14.4	II	
1.2	6	13	8.7	II	
1.2	8	13	11.6	II	
1.2					
1.3	6	13	8.7	II	
1.3					
1.4	10	13	14.4	II	
1.4	20	13	28.9	IV	
1.4	6	13	8.7	II	
1.4	25	13	36.1	IV	14
1.5	10	13	14.4	II	
1.5	12	13	17.3	III	
1.5	4	13	5.8	II	
1.5	6	13	8.7	II	
1.6	25	13	36.1	IV	14
SHEET TOTALS:			312.0		28

• MILEPOST BEGINS AT THE NORTH PROJECT TERMINUS AND GOES SOUTH.
 PATCHING SURVEY QUANTITIES FOR INFORMATION ONLY. ACTUAL QUANTITIES AND LOCATIONS SHALL BE DETERMINED BY ENGINEER IN FIELD.