


DUCT MARKERS SHALL BE RECESSED AND GROUTED INTO THE PAVEMENTS.

SECTION

MARKER PLACEMENT

DUCT MARKER DETAILS

N.T.S.



DUCT BANK DETAIL N.T.S.

DUCT BANK NOTES

- 1. DIMENSIONS SHOWN ARE MINIMUM.
- 2. TOP OF CONCRETE ENCASEMENT TO BE NOT LESS THAN 18" BELOW FINISHED SUBGRADE.
- 3. DUCT CONCRETE SHALL BE ITEM 610 STRUCTURAL P.C.C. CONCRETE.
- 4. ALL DUCT SHALL BE 4" INSIDE DIAMETER.
- 5. LOCATIONS SHOWN ARE APPROXIMATE. DUCT BANKS SHALL BE INSTALLED AT LOCATIONS DESIGNATED BY THE ENGINEER.
- CONTRACTOR SHALL INSTALL DUCT BANKS AT A DEPTH WHICH WILL NOT CONFLICT WITH ELEVATION SENSITIVE UTILITIES.
- A PULL WIRE SHALL BE PROVIDED IN EACH UNUSED CONDUIT. UNUSED DUCT SHALL BE SEALED WITH PVC PLUGS/CAPS TO THE SATISFACTION OF THE ENGINEER.
- 8. DUCT BANKS SHALL EXTEND A MINIMUM OF 5' BEYOND THE NEW EDGE OF PAVEMENT.

FILE: UPD/ PLOT	DUCTE ATE BY: DATE:	Kristy 1/21/	Ldwg Brod	eets\Phase 2	
CA007 REVISIONS					
NUMBER B				DATE	
		 			
		<u> </u>			
	0		-N	2	
THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).					
(4)			•
SPRINGFIELD AIRPORT AUTHORITY	AHAM LINCOLN CAI		WIDEN TAXIWAY G - PHASE 2	DUCT BANK DETAIL	
O Copyright CAT, Inc.	5	CONSULTING ENGMERS License No. 184-000613			
DES	IGN BY	:	CBG		
DRA	WN BY		CMT		
	***************************************	BY:	RUN	<u> </u>	
DAT	ROVED	BY:	01/3	30/2009	
J08			-	5-09-00	
IL. PROJ. NO. SPI-3860					

AIP PROJ. NO. 3-17-0096-XX

SHEET 53 OF 65 SHEETS