


CA007

REVISIONS		
NUMBER	BY	DATE



SPRINGFIELD AIRPORT AUTHORITY
 ABRAHAM LINCOLN CAPITAL AIRPORT
 SPRINGFIELD, ILLINOIS

WIDEN TAXIWAY G - PHASE 2
 EARTHWORK SUMMARY

© Copyright CMT, Inc.
CMT
 CRAWFORD, MURPHY & TILLY, INC.
 CONSULTING ENGINEERS
 License No. 94-000613



DESIGN BY:	CBG
DRAWN BY:	CMT
CHECKED BY:	<i>REN</i>
APPROVED BY:	<i>REN</i>
DATE:	01/30/2009
JOB No:	07035-09-00
IL PROJ. NO.	SPI-3860
AIP PROJ. NO.	3-17-0096-XX
SHEET	58 OF 65 SHEETS

EARTHWORK SUMMARY

STATION	EXCAVATE END AREA (S.F.)	EMBANK END AREA (S.F.)
---------	--------------------------------	------------------------------

TAXIWAY G WIDENING		
1177+09.39	27.77	0.00
1177+50	129.80	0.00
1178+00	131.32	0.00
1178+50	136.50	0.00
1179+00	50.35	0.00
1179+50	135.87	0.00
1180+00	111.05	0.00
1180+50	86.56	0.00
1181+00	88.64	1.95
1181+50	94.23	1.99
1182+00	55.66	0.02
1182+50	49.44	0.00
1183+00	71.97	0.00
1183+50	100.40	0.00
1184+00	91.04	0.00
1184+50	96.95	2.65
1185+00	98.53	1.47
1185+50	99.32	0.62
1186+00	85.59	1.04
1186+50	84.12	1.23
1187+00	96.44	0.57
1187+50	95.99	0.59
1188+00	72.19	0.44
1188+50	58.56	10.15
1189+00	48.30	10.49
1189+50	48.21	16.60
1190+00	46.61	21.89
1190+50	48.82	26.34
1191+00	53.45	25.88

EARTHWORK SUMMARY

STATION	EXCAVATE END AREA (S.F.)	EMBANK END AREA (S.F.)
---------	--------------------------------	------------------------------

1191+50	57.90	20.42
1192+00	58.40	11.51
1192+50	67.00	4.28
1193+00	70.45	3.85
1193+50	55.47	1.94
1194+00	79.66	0.42
1194+50	71.08	1.20
1195+00	57.06	17.53
1195+50	63.78	25.62
1196+00	54.85	8.74
1196+50	50.58	19.59
1197+00	53.32	6.16
1197+50	66.45	6.42
1197+68.85	68.43	7.49

TAXIWAY Z REHAB		
0+37.5	141.26	0.00
0+50	115.18	0.00
1+00	24.58	0.49
1+50	78.40	1.43
2+00	0.00	0.00
2+50	0.00	4.06
3+00	10.74	9.23
3+50	5.47	14.04
4+00	1.06	16.12
4+50	1.93	14.13
5+00	9.22	8.70
5+44.19	26.00	4.08

NOTES

- CROSS SECTIONS 1183+50 TO 1188+00 REFLECT EARTHWORK CALCULATIONS BEYOND THE GRADING LIMITS SHOWN IN THE CROSS SECTIONS.