INDEX OF SHEETS

1 COVER SHEET

2008 INDEX, STANDARDS, CENERAL NOTES, SIGNATURES, & SUMMARY OF QUANTITIES

3-4 BRIDGE LOCATION MAPS

5-21 EXISTING BRIDGE PLANS (FOR INFORMATION ONLY)

701101-04 701106-02 701400-08 701401-09 701901-04 101001-02 701006-05 BLR21-9

## GENERAL NOTES:

1. STRUCTURES TO BE PAINTED SHALL BE AS SPECIFIED ON THE PLAN SHEETS. CLEANING AND PAINTING OF THE EXISTING STRUCTURAL STEEL SHALL BE AS SPECIFIED IN THE SPECIAL PROVISIONS FOR "CLEANING AND PAINTING EXISTING STEEL STRUCTURES". THE AREAS TO BE PAINTED ON EACH BRIDGE SHALL BE AS SPECIFIED ON THE PLAN SHEETS. ALL AREAS TO BE PAINTED SHALL SHALL BE CLEANED PER NEAR WHITE BLAST CLEANING PER SSPC SP 10. ALL EXISTING STEEL CLEANED SHALL BE PAINTED ACCORDING TO THE REQUIREMENTS OF PAINT SYSTEM 1 - 0Z/E/U. THE COLOR OF THE FINAL FINISH COAT FOR EACH BRIDGE SHALL BE AS SPECIFIED ON THE PLAN SHEETS. THE COLORS SPECIFIED ON THE PLAN SHEETS SHALL CORRESPOND WITH THE COLOR SPECIFICATIONS SHOWN IN THE TABLE ON THIS PAGE.

2 THE USE OF AIR MONITORS WILL BE REQUIRED AT STRUCTURES SPECIFIED ON THE PLAN SHEETS. A MINIMUM OF 2 MONITORS WILL BE REQUIRED AT EACH SPECIFIED BRIDGE TO MONITOR ABRASIVE BLASTING OPERATIONS AT THOSE SITES, SEE SPECIAL PROVISIONS FOR "CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES".

- 3. THE SSPC-OP-1 AND SSPC-OP2 PAINTING CONTRACTOR CERTIFICATIONS WILL BE REQUIRED FOR THESE BRIDGES.
- 4. CARE SHALL BE TAKEN NOT TO DAMAGE RUBBER BEARING OR JOINT COMPONENTS DURING BLASTING AND CLEANING OPERATIONS. ANY DAMAGE TO THESE COMPONENTS SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
- 5. UPON COMPLETION OF PAINTING OPERATIONS AT EACH LOCATION. THE CONTRACTOR SHALL REMOVE ALL DEBRIS FROM PIER OR ABUTMENT CAPS UPON WHICH PAINTING OPERATIONS TOOK PLACE. FINAL CLEANUP SHALL BE CONSIDERED INCIDENTAL TO THE PAINT PAY ITEM FOR THE RESPECTIVE LOCATION. THE ENGINEER SHALL HAVE THE RIGHT TO WITHOLD PAYMENT UNTIL SATISFACTORY CLEANUP IS ACHIEVED.
- 6. NO LANE CLOSURES WILL BE PERMITTED FOR STRUCTURES 1 THROUGH 6. ALL WORK AT THESE STRUCTURES SHALL BE PERFORMED UNDER SHOULDER CLOSURES.
- 7. ANY DAMAGE TO THE EXISTING RIGHT OF WAY DUE TO THE CONTRACTOR'S ACTIVITIES SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE. REPAIRS SHALL INCLUDE BUT NOT BE LIMITED TO REGRADING AND RESEEDING DISRUPTED AREAS AND SHALL BE AT THE DIRECTION OF THE ENGINEER.

COLOR SPECIFICATION TABLE				
COLOR SPECIFIED	COLOR SPECIFICATION			
GRAY	MUNSELL 5B 7/1			
GREEN	MUNSELL 7.5G 4/8			

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS DISTRICT 6			
EXAMINED SCORMER & 26 14  Ale C. Nagruyan  ENGINEER OF OPERATIONS			
EXAMINED December 4 20/4  Son Suchambean ENGINEER OF PROJECT IMPLEMENTATION			
EXAMINED December 4 20 14  Jeff P. Myen ENGINEER OF PROGRAM DEVELOPMENT			

CONSTR. CODE 100% STATE BRIDGE CODE TOTAL 0014 ITEM NO. UNIT QUANTITY VARIOUS 67100100 MOBILIZATION L SUM 70100800 TRAFFIC CONTROL AND PROTECTION, STANDARD TO140 L SUM TOIDI830 TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21 L SUM 70106800 CHANGEABLE MESSAGE SIGN CAL MO TEMPORARY WATER FILLED BARRIER FOOT 500 500 Z0007101 CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. L SUM 1 1 70007102 CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 2 L SUM Z0007103 CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 3 L SUM 1 Z0007104 CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 4 L SUM 20007105 CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 5 L SUM 20007106 CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 6 L SUM 1 Z0007107 CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 7 L SUM 20010501 CLEANING AND PAINTING STEEL BRIDGE NO. 1 L SUM Z0010502 CLEANING AND PAINTING STEEL BRIDGE NO. 2 L SUM Z0010503 CLEANING AND PAINTING STEEL BRIDGE NO. 3 L SUM Z0010504 CLEANING AND PAINTING STEEL BRIDGE NO. 4 L SUM Z0010505 CLEANING AND PAINTING STEEL BRIDGE NO. 5 L SUM 20010506 CLEANING AND PAINTING STEEL BRIDGE NO. 6 L SUM 1 70010507 CLEANING AND PAINTING STEEL BRIDGE NO. T L SUM Z0048665 RAILROAD PROTECTIVE LIABILITY INSURANCE L SUM 1

A REV. 2-23-15

FILE NAME .	USER NAME * dudlaybm	DESIGNED -	REVISED -	7
Or/OPERATIONS\Bridges\Bridgeslane_CAO\7;	056-06 Bridge Painting 2014-11-revised contro	OPAWWA plansheetydgo	REVISED -	7
	PLOT SCALE . 100,0000 ' / in.	CHECKED -	REVISED -	
Default	PLOT DATE + Dec-12-2014 83:85:51PM	DATE -	REVISED -	٦

INDEX OF SHEETS, STANDARDS, GENERAL NOTES,	F.A. SECTION	COUNTY TOTAL SHEET SHEET NO.
SIGNATURES, & SUMMARY OF QUANTITITES	VAR. DE BRIDCE PAINTING 2014-1	MONT./SANG. 21 2
		CONTRACT NO. 72C56
SCALE: SHEET OF SHEETS STA TO STA	ILLINOIS FED. AID	PROJECT