



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 27, 2020

SUBJECT: FAU Route 2710 (Des Plaines River Rd)
Project STP-95BX(149)
Section 2019-098-RS-SW& SR
Cook County
Contract No. 62J88
Item No. 25, March 6, 2020
Letting Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page ii of the Table of Contents to the Special Provisions
3. Added pages 116 & 117 to the Special Provisions
4. Revised sheets 1-21 of the Plans
5. Added sheets 312A-31F to the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

EMULSIFIED ASPHALTS (BDE)	66
ENGINEER’S FIELD OFFICE AND LABORATORY (BDE)	69
EQUIPMENT PARKING AND STORAGE (BDE)	72
FUEL COST ADJUSTMENT (BDE)	72
GROOVING FOR RECESSED PAVEMENT MARKINGS (BDE).....	75
HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE).....	77
HOT MIX ASPHALT - PAY FOR PERFORMANCE USING PERCENT WITHIN LIMITS - JOBSITE SAMPLING (BDE)	81
HOT MIX ASPHALT – QUALITY CONTROL FOR PERFORMANCE (BDE)	86
MANHOLES, VALVE VAULTS, AND FLAT SLAB TOPS (BDE)	91
PORTLAND CEMENT CONCRETE (BDE)	92
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	93
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	103
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....	104
TEMPORARY PAVEMENT MARKING (BDE).....	104
TRAFFIC CONTROL DEVICES - CONES (BDE).....	107
TRAINING SPECIAL PROVISIONS (BDE)	107
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION.	110
WARM MIX ASPHALT (BDE)	112
WEEKLY DBE TRUCKING REPORTS (BDE).....	113
WORK ZONE TRAFFIC CONTROL DEVICES (BDE).....	114
REBUILD EXISTING HANDHOLE	116
REBUILD EXISTING HANDHOLE TO HEAVY-DUTY HANDHOLE	117

Revised 2/27/2020

REBUILD EXISTING HANDHOLE

Effective: January 1, 2002
895.04TS

Revised: July 1, 2015

This item shall consist of rebuilding and bringing to grade a handhole at a location shown on the plans or as directed by the Engineer. The work shall consist of removing the handhole frame and cover and the walls of the handhole to a depth of eight (8) inches below the finished grade.

Upon completion of the above work, four (4) holes, four (4) inches in depth and one half (1/2) inch in diameter, shall be drilled into the remaining concrete; one hole centered on each of the four handhole walls. Four (4) #3 steel dowels, eight (8) inches in length, shall be furnished and shall be installed in the drilled holes with a masonry epoxy.

All concrete debris shall be disposed of outside the right-of-way.

The area adjacent to each side of the handhole shall be excavated to allow forming. All steel hooks, handhole frame, cover, and concrete shall be provided to construct a rebuilt handhole according to applicable portions of Section 814 of the Standard Specification and as modified in 814.01TS HANDHOLES Special Provision. The existing frame and cover shall be replaced if it was damaged during removal or as determined by the Engineer.

Basis of Payment.

This work shall be paid for at the contract unit price each for REBUILD EXISTING HANDHOLE, which price shall be payment in full for all labor, materials, and equipment necessary to complete the work described above and as indicated on the drawings.

Added 2/27/2020

REBUILD EXISTING HANDHOLE TO HEAVY-DUTY HANDHOLE

Effective: January 1, 2002
895.05TS

Revised: July 1, 2015

This item shall consist of partial removal of an existing concrete traffic signal handhole, reconstruction to the specifications of heavy duty handhole including new frame and cover, and bringing it to grade at location(s) shown in the plans or as directed by the Engineer. This work shall consist of removing the existing handhole frame and cover and the walls of the handhole to a depth of fifteen (15) inches below the finished grade.

Upon completion of the above work, four (4) holes, four (4) inches in depth, and one-half (1/2) inch in diameter shall be drilled into the top of the remaining concrete; one hole centered into each of the four handhole walls. Four (4) #3 steel dowels eight inches in length, shall be furnished and installed in the drilled holes with a masonry epoxy.

All concrete debris shall be disposed of outside the right-of-way.

Any pavement or asphalt surface removal required to install the new concrete shall have straight and neat edges using a method approved by the Engineer. Care shall be taken to protect the existing traffic signal cable. Any cable damage shall be reported immediately and repaired as directed by the Area Traffic Signal Engineer.

All steel hooks, handhole frame, cover, and concrete shall be provided to construct a rebuilt heavy duty handhole according to applicable portions of Section 814 of the Standard Specification and as modified in 814.01TS HANDHOLES Special Provision.

Basis of Payment.

This work shall be paid for at the contract unit price each for REBUILD EXISTING HANDHOLE TO HEAVY-DUTY HANDHOLE.

Added 2/27/2020