

INDEX OF SHEETS

SHEET NO	DESCRIPTION
1	COVER SHEET
2	SIGNATURE SHEET
3	INDEX OF SHEETS, GENERAL NOTES, STANDARDS
4	SUMMARY OF QUANTITIES
5	PROPOSED PATCHING
6	STANDARD 2224-B 24 FT CRC PAVEMENT -1965
7	STANDARD 2225-5 REINFORCEMENT FOR CRC PAVEMENT - 1965

GENERAL NOTES

QUANTITIES SHOWN IN THE PLANS FOR PATCHING ARE ESTIMATES. THE ACTUAL AMOUNT OF PATCHING REQUIRED WILL BE DETERMINED BY THE ENGINEER.

IF BASE REPAIR IS NEEDED FOR A PROPOSED PATCH, THE WORK SHALL BE PAID FOR IN ACCORDANCE WITH ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS.

COMMITMENTS: NONE

HIGHWAY STANDARDS

000001-07	STANDARD SYMBOLS AND ABBREVIATIONS & PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
421101-10	24' CRC PAVEMENT (WITH WIDE FLANGE BEAM TERMINAL JOINT)
421201-07	24' CRC PAVEMENT (WITH LUG SYSTEM)
442001-04	CLASS A PATCHES
442101-09	CLASS B PATCHES
701101-05	OFF-ROAD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE OFF
701106-02	OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 15' AWAY
701422-10	LANE CLOSURE, MULTILANE, FOR SPEEDS $\geq$ 45 MPH TO 55 MPH
701421-08	LANE CLOSURE, MULTILANE, DAY OPERATIONS ONLY, FOR SPEEDS $\geq$ 45 MPH TO 55 MPH
701901-08	TRAFFIC CONTROL DEVICES
701601-09	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN



REV. 2-25-2020

REV. - MS

Model: Default  
File: \\state-pw\jlanonm-dot\illinois.gov\HWDOT\Documents\DOT\_Offices\District\_9\Projects\78766\CADDData\CAD\Sheets\DS78766-Sheets.dgn

	USER NAME = poesi	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS					F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -		GENERAL NOTES, HIGHWAY STANDAR					331	D9 CM PAVT JOINT REPAIR 2020-1	WILLIAMSON	7	3
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -							CONTRACT NO. 78766				
	PLOT DATE = 12/11/2019	DATE -	REVISED -							ILLINOIS FED. AID PROJECT				
					SCALE:	SHEET	OF	SHEETS	STA.	TO STA.				

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROUTE:	FAP 103 ( IL 13 )	
				COUNTY:	WILLIAMSON	
				FUNDING:	100% STATE	
				LOCATION:	RURAL	RURAL
				LOCATION:	LOCATION 1	LOCATION 2
					ROADWAY	ROADWAY
					0006	0006
44200610	CLASS A PATCHES, TYPE II, 13 INCH	SQ YD	22			22
44201007	CLASS B PATCHES, TYPE II, 13 INCH	SQ YD	44		22	22
44201299	DOWEL BARS 1 1/2"	EACH	80		40	40
44213000	PATCHING REINFORCEMENT	SQ YD	22			22
44213200	SAW CUTS	FOOT	200		104	96
67100100	MOBILIZATION	L SUM	1.0		0.3	0.7
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1.0		0.3	0.7
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	40		18	22
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1.0		0.3	0.7
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1.0		0.3	0.7

1

REV. 2-25-2020

MODEL: Default  
FILE: Model - pav100000.dwg  
PROJECT: 78766  
SHEET: 4  
DATE: 12/11/2019

USER NAME = poesl	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000" / in.	CHECKED -	REVISED -
PLOT DATE = 12/11/2019	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	09 CM PAVT JOINT REPAIR 2020-1	WILLIAMSON	7	4
CONTRACT NO. 78766				
ILLINOIS FED. AID PROJECT				