

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1707	D7 AGG SHLD 2020-1	CLARK	4	1
		ILLINOIS	CONTRACT NO. 74936	

129

FOR INDEX OF SHEETS, SEE SHEET NO. 2



ADT=4,000 (2017)

PROPOSED HIGHWAY PLANS

FAS ROUTE 1707 (US 40) SECTION D7 AGG SHLD 2020-1 SHOULDER RECONSTRUCTION CLARK COUNTY

C-97-012-20

D-97-012-20



FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

J.U.L.I.E.
JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS
1-800-892-0123
OR 811

PROJECT ENGINEER: THOMAS RONAN
PROJECT MANAGER: HANNAH DAVIDSON
PHONE: (217) 342-8320

CONTRACT NO. 74936

NET LENGTH = 140,606.40 FT. = 26.63 MILES

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUBMITTED November 20 20 19
Jeffrey P. Mysela
REGIONAL ENGINEER

Jan 31 20 20
CO. E.A. CTS
ENGINEER OF DESIGN AND ENVIRONMENT

Jan 31 20 20
Thomas Ronan
DIRECTOR OF HIGHWAYS PROJECT IMPLEMENTATION

PRINTED BY THE AUTHORITY
OF THE STATE OF ILLINOIS

INDEX OF SHEETS

SHEET NO.	ITEM
1	COVER SHEET
2	INDEX OF SHEETS, GENERAL NOTES AND SHOULDER DETAIL
3	SUMMARY OF QUANTITIES
4	LOCATION MAP

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NO. 4:

STD. NO.	DESCRIPTION
000001-07	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
406201-01	MAILBOX TURNOUT
701001-02	OFF-ROAD OPERATIONS, 2L, 2W, MORE THAT 15' AWAY
701006-05	OFF-RD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE
701011-04	OFF-RD MOVING OPERATIONS, 2L,2W, DAY ONLY
701301-04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701306-04	LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS, DAY ONLY, FOR SPEEDS ≥ 45 MPH
701311-03	LANE CLOSURE, 2L, 2W, MOVING OPERATIONS - DAY ONLY
701901-08	TRAFFIC CONTROL DEVICES

GENERAL NOTES

THIS PROJECT IS LOCATED ON US ROUTE 40 IN CLARK COUNTY. THE PROJECT STARTS AT ILLINOIS ROUTE 49 IN CASEY AND EXTENDS EAST FOR APPROXIMATELY 26.63 MILES TO THE ILLINOIS/INDIANA STATE LINE.

THE WORK INCLUDED IN SECTION D7 AGG SHLD 2020-1 CONSISTS OF PLACING AGGREGATE SHOULDERS, TRAFFIC CONTROL, AND ANY OTHER WORK NECESSARY TO COMPLETE THE SECTION.

ALL MATERIAL USED FOR AGGREGATE SHOULDERS, TYPE A SHALL BE CRUSHED STONE WITH A MINIMUM IBR OF 80.


AGGREGATE FOR MAILBOX TURNOUTS AND PRIVATE ENTRANCES SHALL BE PLACED AS DIRECTED BY THE ENGINEER AND WILL BE PAID FOR AS AGGREGATE SHOULDERS, TYPE A.

A RATE OF APPLICATION OF 1.8 TONS/CU YD FOR GRANULAR MATERIAL HAS BEEN USED IN CALCULATING PLAN QUANTITY.

OMISSIONS

GENERAL OMISSIONS WILL BE PAVED SECTIONS OF SHOULDER INCLUDING SIDE ROADS AND INTERSECTIONS, PRIVATE ENTRANCES, FIELD ENTRANCES, COMMERCIAL ENTRANCES, AND MAILBOX TURNOUTS.

SHOULDER DETAIL



EASTBOUND OMISSIONS

STATION	TO	STATION
2810+04.00		2813+79.00
2865+90.50		2867+35.50
2944+87.00		2946+97.00
3181+94.61		3189+64.61
3298+25.00		3302+00.00
3564+84.50		3570+34.50
3614+97.85		3616+87.85
3830+90.00		3867+00.00

WESTBOUND OMISSIONS

STATION	TO	STATION
2810+04.00		2813+79.00
2865+78.50		2867+23.50
2940+90.00		2955+10.00
3182+89.61		3189+89.61
3298+30.00		3301+00.00
3372+13.00		3379+93.00
3549+25.50		3552+63.50
3564+79.50		3570+29.50
3615+12.85		3617+02.85
3830+00.00		3867+00.00

MODEL: Default
FILE: h:\m\c\p\pub\h\m\room\dat\illinois.gov\RWIDOT\Documents\IDOT_Offices\IDOT\74936\CADD\DATA\CAD\sheet\ID74936-shl-geomote.dgn

USER NAME = steffemk	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 11/22/2019	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**INDEX OF SHEETS, GENERAL NOTES
AND SHOULDER DETAIL**

SCALE: N/A SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1707	D7 AGG SHLD 2020-1	CLARK	4	2
CONTRACT NO. 74936				
ILLINOIS		FED. AID PROJECT		

