INDEX OF SHEETS

SHEET NO.	DESCRIPTION			STATE STANDARDS	
· 1	TITLE SHEET		000001-05	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS	
2	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES		642001	SHOULDER RUMBLE STRIPS	
3	SUMMARY OF QUANTITIES		701400-02	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY	
4-24	ROADWAY PLANS		701401-04	LANE CLOSURE, FREEWAY/EXPRESSWAY	
			701411-04	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS 245MPH	
			701901	TRAFFIC CONTROL DEVICES	

GENERAL NOTES:

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED)

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE CITY OF CHICAGO AND THE VILLAGES OF STICKNEY, FOREST VIEW, SUMMIT, BEDFORD PARK, HODGKINS AND COUNTRYSIDE.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

BARRICADES: THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO
(2) WEIGHTED SANDBAGS ON EACH TYPE I, TYPE II OR TYPE III BARRICADE
USED- ONE (1) WEIGHTED SAND BAG ACROSS EACH BOTTOM RAIL.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE ARTERIAL TRAFFIC CONTROL SUPERVISOR A MINIMUM OF 72 HOURS PRIOR TO BEGINNING WORK.

A CONTRACTOR OF THE CONTRACTOR			
FILE NAME =	USER NAME = abreush	DESIGNED -	REVISED -
ci\projects\design\2007\155\155.dgn		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 '/ IN.	CHECKED -	REVISED -
	PLOT DATE = 12/17/2007	DATE -	REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

	1		
I55 from Willow Springs Rd. to California Ave.	F.A.I RTE.	SECTION	COUNTY
INDEX OF SHEETS STATE STANDARDS AND GENERAL NOT	-C 55	2007-046 I	COOK
INDEX OF SHEETS STATE STANDARDS AND GENERAL NOT	ES	-	CONTRACT
SCALE: 1" = 50' SHEET NO. OF SHEETS STA. TO STA.	FED.	ROAD DIST. NO. 1 ILLINOIS FED. A	ID PROJECT