

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2 SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

	REVISIONS		
	NAME	DATE	
	R. MIRS	9-15-97	
	R. MIRS	12-11-97	
	T. RAMMACHER	2-2-99	
	C. JUCIUS	1-31-07	
L_			
			SCA
			JCAI

ILLINOIS DEPARTMENT OF TRANSPORTATION

ARTERIAL ROAD INFORMATION SIGN

CALE: NONE

DRAWN BY DESIGN CHECKED BY

TC22

PLOT DATE = 9/11/2007 FILE NAME = o:\pro.glocts\pi001694\design=bb.m PLOT SCALE = 50.000 \(\) IN, USER NAME = hamdenah