
\*(125BR-1)D

DD CONTRACT NO. 64D10



## NOTES

Detail I - With Bar Splicer or Couplers:

Connect one (1) 1"x7"x10" steel ₱ to the
top layer of couplers with 2-5<sub>8</sub>" \$\phi\$ bolts
screwed to coupler at approximate \$\mathbb{Q}\$ of
each barrier panel.

Detail II - With Extended Reinforcement Bars:

Connect one (1) 1"x7"x10" steel £ to the concrete slab or concrete wearing surface with 2-5g" 

Expansion Anchors or cast in place inserts 
spaced between the top layer of reinforcement 
at approximate £ of each barrier panel.


Cost of anchorage is included with Temporary Concrete Barrier.
The 1" x 7" x 10" plate shall not be removed until stage II construction forms and all reinforcement bars are in place and the concrete is ready to be placed.


## SECTIONS THRU SLAB OR DECK BEAM

\*\*\*Dimension shown is minimum required embedment into concrete.


If hot-mix asphalt wearing surface is present, minimum embedment shall be in addition to wearing surface depth.

\*\*\*\*If existing deck beam is to remain in place after stage construction,






<u>DETAIL I</u>



\*\*Wood blocks may be omitted when required to provide minimum stage traffic lane width. When the wood blocks are omitted, the concrete barrier shall be in direct contact with the steel retainer plate.



## STEEL RETAINER P 1" x 7" x 10"

\* Required only with Detail II

TEMPORARY CONCRETE BARRIER
FOR STAGE CONSTRUCTION
FAP 22 (ILLINOIS ROUTE 78)
OVER GREEN RIVER
SEC. (125BR-1)D
HENRY COUNTY
STATION 882+67.79
STR. NO. 037-0129

HUTCHISON ENGINEERING, INC.

JACKSONVILLE, ILLINOIS
Date:

[	
DESIGNED	BAN
CHECKED	JOH
DRAWN	TD
CHECKED	BAN

R-27

9-3-07