SUMMARY OF QUANTITIES

	SUMMARY OF QUANTITIES		10% STATE	CONSTRUCTION X031-2A	X031-2A	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES			
0603090 14000157	HOT-MIX ASPHALT DINDER COURSE, IL-19.0, N90 HOT-MIX ASPHALT SURFACE REMOVAL, 2"	TON SQ YD	77 <i>5</i> 5592	77 <i>5</i> 5592		
18203100	HOT-MIX ASPHALT SHOULDERS	-TON-	-775	-775		
50102400	CONCRETE REMOVAL	CU YD	45	45		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	122.9	122.9		
50300260	BRIDGE DECK GROOVING	SQ YD	131	131		
50300300	PROTECTIVE COAT	SQ YD	146	146		
50606401	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1			
0606402 50800205	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING REINFORCEMENT BARS, EPOXY COATED RESIDUES NO. 2	L SUM. POUND	1 16040	16040		
50800515	BAR SPLICERS	EACH	52	52		
50260100	INLETS TO BE ADJUSTED	EACH	7	7		
57000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7		
37100100	MOBILIZATION	L SUM	1	1		
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 70140/	L SUM				
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1145	1145		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	24793	24793		
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE	F00T	1850	1850		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	8264	8264		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	950	950		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	900	900		
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	8667	8667		
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	124	124		
78100300	REPLACEMENT REFLECTOR	EACH	248	248		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2889	2889		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	248	248		
20030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
20030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2 2		
0600600	CLEANING AND PAINTING STEEL BRIDGE NO. 1	LSUM				
0600700	물리가는 기다리는 경험 이번 가장하다 하기를 통해 되었다고 있다.	L SUM				

FILE NAME =

USER NAME = harbaughrd

PLOT SCALE = 50.0000 / IN.

PLOT DATE = 12/19/2007

DESIGNED

CHECKED

DRAWN

DATE

REVISED

REVISED

REVISED

REVISED

GENERAL NOTES:

- 1. THE STANDARDS AND REVISION NUMBERS LISTED SHALL APPLY TO THIS PROJECT.
- 2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
- 3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITES WITHIN THE PROJECT AREA BEFORE DIGGING BY CALLING J.U.L.I.E. AND BY NOTIFYING NON-J.U.L.I.E. MEMBERS INDIVIDUALLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - * AMERENIP (GAS & ELECTRIC)
 - * AT&T CORPORATION (COMMUNICATIONS)
 - * CHARTER COMMUNICATIONS, INC. (CABLE TV)
 - * ILLINOIS AMERICAN WATER COMPANY (WATER)
 - * AT&T ILLINOIS (COMMUNICATIONS)

MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY*. NON-MEMBERS MUST BE NOTIFIED INDIVIDUALLY.

- 4. THE CONTRACTOR SHALL FURNISH AND INSTALL WOOD SIGN SUPPORTS IN ACCORDANCE WITH SECTION 730 OF THE STANDARD SPECIFICATIONS; HOWEVER, INSTALLATION BY METHOD 'A' (ARTICLE 730.04(a)) SHALL BE THE ONLY METHOD PERMITTED.
- 5. FOR STAGE I, THE BOTTOM 6" OF THE TEMPORARY CONCRETE BARRIER SHALL BE PAINTED YELLOW, FOR STAGE II, THE BOTTOM 6" OF THE TEMPORARY CONCRETE BARRIER SHALL BE PAINTED WHITE. THE COST SHALL BE PAID FOR AS "TEMPORARY PAINT PAVEMNET MARKING - LINE 6" ".
- 6. PAVMENT MARKING REMOVAL SHALL BE BY WATER BLAST METHOD.
- 7. TWO LANE TRAFFIC IN EACH DIRECTION SHALL BE MAINTAINED AT ALL TIMES.
- 8. 'ROAD CONSTRUCTION AHEAD' AND 'WORK ZONE SPEED LIMIT' SIGNS SHALL BE INSTALLED AS DIRECTED BY THE RESIDENT ENGINEER ON THE SOUTHBOUND RAMP AT IL 162.

COMMITMENTS

* SPECIALTY ITEMS SUMMARY OF QUANTITIES, GENERAL NOTES & COMMITMENTS

SHEET NO. 2 OF 42 SHEETS STA.

COUNTY TOTAL SHEE NO. SECTION 60-8B-1I MADISON 42 255 CONTRACT NO. 76A25

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION