SECTION COUNTY 19 3 06-00314-00-RS PEORIA FED. ROAD DIST. NO. ILLINOIS CONTRACT # 89455

0.5% MIN. SLOPE (TYP.) -12" MIN. COVER FROM INLET TYPE A SURFACE OF PAVEMENT (TYP.) TO TOP OF CULVERT PIPE MATCH EXISTING DITCH FLOWLINE

TYPICAL CULVERT CROSSING

NOT TO SCALE

PROPOSED HMA SURF CSE 2" -1.5'

> **BUTT JOINT DETAIL** NOT TO SCALE.

PAVEMENT DESIGN

STRUCTURAL DESIGN TRAFFIC (S.D.T.): YEAR 2027; (ALL STREETS) P.C. 114 CLASS IV ROAD (OR STREET) S.U. 2 M.U. 0


MINIMUM SOIL SUPPORT: IBR = 2.0

FROM IDOT FIGURE 54-5M, PAGE 54-5 (19) OF THE BUREAU OF DESIGN AND ENVIRONMENT MANUAL, THE REQUIRED STRUCTURAL NUMBER IS 1.5. THIS REQUIREMENT IS SATISFIED BY THE FOLLOWING:

BIT. SURF. CSE. : T1 = 2.0" A1 = 0.40

AGG. BASE CSE. : T4 = 8" A4 = 0.10


STRUCTURAL NO. PROVIDED = T1 * A1 + T2 * A2 = 1.6 > 1.5 (REQ.)



NOTE:

PROPOSED GUTTER TO MATCH PROPOSED EDGE OF PAVEMENT. ANY LOCALIZED DEPRESSIONS IN THE ROADWAY SHALL BE FILLED AND LEVELED CONCURRENT WITH GUTTER CONSTRUCTION. COST WILL BE PAID FOR AS LEVEL BINDER HM N30.

EXISTING AGGREGATE SHOULDER / GROUTED COBBLES SHALL BE REMOVED TO ALLOW FOR STANDARD PLACEMENT OF THE GUTTER TYPE B. ADDITIONAL EXCAVATION, HAND TRIMMING OF THE CUT, ETC. SHALL BE INCLUDED IN THE COST OF SHOULDER REMOVAL.



TYPICAL SECTION

ROSE HILL

STA 0+00 TO 0+75 STA 5+00 TO 18+90

HERVEY LIGHTNER

STA 3+00 TO 24+50

MEMORIAL LANE

STA 0+50 TO 22+00

L				
REVISIONS				DESIGNEDAJS
NO.	DATE	DESCRIPTION	APPROVED	DRAWN AJS, KSB, JLA
				CHECKEDEEA
				DATE 01/04/0%



