

MARKING SCHEDULE

LOCATION STATION TO STATION	TEMP PVT MK LINE 4' '		PAINT PVT MK LINE 4' '		SHORT -TERM PAVEMENT MARKING FOOT	PAVEMENT MARKING REMOVAL SQ FT
	WHITE	YELLOW	WHITE	YELLOW		
	FOOT	FOOT	FOOT	FOOT		
FAS 726 (IL 37)						
PRE STAGE I						
CL STA 527+75 TO 530+25						105
LT STA 529+92 TO 533+77	385					129
CL STA 533+50 TO 536+00						57.5
STAGE I						
CL STA 528+70 TO 534+95		625				
RT STA 529+65 TO 530+74						36.25
RT STA 532+88 TO 533+85						32.25
STAGE II						
RT STA 529+65 TO 533+85	420					
CL STA 528+70 TO 534+95		625				
POST STAGE II						
CL STA 527+69 TO 536+00					90	
LT STA 527+69 TO 535+09			740			
RT STA 527+69 TO 535+09			740			
STA 527+69 TO 530+25 (CL DASH + SOLID)				320		
STA 530+25 TO 533+50 (CL DOUBLE)				650		
STA 533+50 TO 536+00 (CL DASH + SOLID)				313		
TOTALS	805	1250	1480	1283	90	360

BRIDGE APPROACH SCHEDULE

LOCATION STATION TO STATION	POROUS GRANULAR EMBANKMENT(SPCL)	BRIDGE DECK GROOVING	BRIDGE APPROACH PAVEMENT	PROTECTIVE COAT
	CU YD	SQ YD	SQ YD	SQ YD
IL 37				
STA 530+91.50 TO 531+21.50	130		138	
STA 532+40.50 TO 532+70.50	130		138	
STA 530+76.10 TO 531+21.50		207		220
STA 532+40.50 TO 532+85.89		207		220
TOTALS	260	414	276	440

BRIDGE DECK GROOVING AND PROTECTIVE COAT QUANTITIES ARE FOR APPROACH PAVEMENTS AND CONNECTORS ONLY

SHOULDER SCHEDULE

LOCATION STATION TO STATION	HOT-MIX ASPHALT SHOULDERS 8' '	HOT-MIX ASPHALT SHOULDERS 10' '	AGGREGATE SHOULDERS TYPE A, 8' '	HOT-MIX ASPHALT BASE COURSE WIDENING - 10' '
	SQ YD	SQ YD	SQ YD	SQ YD
FAS 726 (IL 37)				
PRE STAGE I				
LT STA 529+92 TO 531+63				75
LT STA 532+19 TO 533+65				70
STAGE I				
RT STA 528+24 TO 529+65	102			
RT STA 530+74 TO 531+06.25	9			
RT STA 532+27.33 TO 532+88	15			
RT STA 533+85 TO 534+54	34			
RT STA 529+65 TO 530+74		136		
RT STA 532+88 TO 533+85		109		
RT STA 528+24 TO 529+06			44	
RT STA 533+72 TO 534+13			21	
RT STA 534+26 TO 534+54			16	
STAGE II				
LT STA 528+24 TO 531+34.33	182			
LT STA 532+33.66 TO 534+54	209			
LT STA 528+24 TO 529+87			91	
TOTALS	551	245	172	145

HOT-MIX ASPHALT SCHEDULE

LOCATION STATION TO STATION	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N90	BITUMINOUS MATERIALS (PRIME COAT)
	TON	TON	GALLON
STA 527+69 TO 528+24		14	
STA 528+24 TO 530+76		47	
STA 532+85.89 TO 534+54		32	
STA 534+54 TO 535+09		13	
STA 527+99 TO 530+76	109		
STA 532+85 TO 534+76	98		
STA 528+24 TO 530+76			40
STA 532+85 TO 534+52			61
TOTALS	207	106	101

SEEDING AND FERTILIZING SCHEDULE

LOCATION STATION TO STATION	SEEDING CLASS 2	SEEDING CLASS 7	NITROGEN (N)	PHOSPHOROUS (P)	POTASSIUM (K)	MULCH METHOD 2	AGRICULTURAL GROUND LIMESTONE	TEMPORARY EROSION CONTROL SEEDING
	ACRES	ACRES	POUND	POUND	POUND	ACRES	TON	POUND
RT STA 528+00 TO 531+00	0.21	0.21	33.6	25	25	0.40	0.42	21
RT STA 532+25 TO 535+00	0.15	0.15	24	18	18	0.26	0.3	15
LT STA 528+00 TO 531+25	0.15	0.15	24	18	18	0.30	0.3	15
LT STA 532+75 TO 534+75	0.09	0.09	14.4	11	11	0.14	0.18	9
TOTALS	0.60	0.60	96	72	72	1.1	1.20	60