

## DETAIL "A"

## TEMPORARY BRACING FOR STAGE I CONSTRUCTION

(No. Required = 6) \*The dimensions "A", "B", and "C" between the holes in the cross frame connection plate and the  $L4x4x_{g}^{3}$ shall be measured in the field. The holes in the brace shall be field drilled at dimensions "C". Included in the cost of "Furnishing and Erecting Structural Steel."



## DETAIL "A" TEMPORARY BRACING FOR STAGE II CONSTRUCTION (No. Required = 6)

## NOTES:

1. Remove Temporary Bracing for Stage II Construction and install typical interior cross frames between girders 3 and 4. Allow at least 72 hours to elapse following the Stage II deck pour prior to removing temporary braces.

2. All materials and installation and removal of temporary braces shall be included in "Furnishing and Erecting Structural Steel."



Note: All steel for flanges, webs, cross frames,

AASHTO M270 Grade 50W.

connection plates, and bearings shall be

\* Fillet weld angles along 3 sides on one face of gusset plate.

\*\* Use 1'2" vertical x <sup>13</sup>16 " slotted holes in connection plates at South side of Beam #3 only. Provide<sup>5</sup><sub>16</sub>" plate washers for slotted holes.





	DELUTATONIA		
	REVISIONS	ILLINOIS DEPARTMENT	OF TRANSPORTATION
	NAME DATE		
		STRUCTURAL ST	TEEL DETAILS
		F.A.P. ROUTE 72	6 (IL. RTE. 37)
		ILLINOIS ROU	TE 37 OVER
		LITTLE SAL.	INE CREEK
		SECTION 113B-2	STA. 531+81.00
& TILLY, INC.		STR. NO. 100-0091 -	WILLIAMSON COUNTY
		SCALE: NONE	DRAWN BY: GLD
<ul> <li>ST. LOUIS, MO</li> <li>CHICAGO, IL</li> </ul>		DATE: 12/14/07	CHECKED BY: WLB