

FILE NAME =

\\pvs\laser\dwg\bering\comp\PILOT\Documents\DOT - Off\asn\0161161.dwg Issues\0161522\CA0Data\Design\0161522-sh-500.dgn

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 80% FED 20% STATE ROADWAY					
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	29228	29228					
40600400	MIXTURE FOR CRACKS, JOINTS & FLANGEWAYS	TON	98	98					
40600370	LONGITUDINAL JOINT SEALANT	FOOT	17219	17219					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT	SO YD	147	147					
	JOINT								
40604062	HOT-MIX ASPHALT SURFACE COURSE, 1L-9.5,	TON	5456	5456					
	MIX "D", N70								
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1	SO YD	64951	64951					
	1/2"								
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	1250	1250					
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SO YD	1250	1250					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	256	256					
44201819	CLASS D PATCHES, TYPE II, 14 INCH	SO YD	1250	1250					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	270	270					
60920012	PIPE CULVERTS TO BE CLEANED 12"	FOOT	346	346					
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	32545	32545					
67100100	MOBILIZATION	L SUM	1	1					
70100450	TRAFFIC CONTROL AND PROTECTION,	L SUM	1	1					
	STANDARD 701201								
70100460	TRAFFIC CONTROL AND PROTECTION,	L SUM	1	1					
	STANDARD 701306								

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	0005 80% FED 20% STATE ROADWAY	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 80% FED 20% STATE ROADWAY					
70100600	TRAFFIC CONTROL AND PROTECTION,	L SUM	1	1					
	STANDARD 701336								
70102635	TRAFFIC CONTROL AND PROTECTION,	L SUM	1	1					
	STANDARD 701701								
70300100	SHORT TERM PAVEMENT MARKING	FOOT	27810	27810					
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SO FT	3090	3090					
70300211	TEMPORARY PAVEMENT MARKING LETTERS AND	SO FT	252	252					
	SYMBOLS - PAINT								
70300221	TEMPORARY PAVEMENT MARKING - LINE 4"-	FOOT	163656	163656					
	PAINT								
70300241	TEMPORARY PAVEMENT MARKING - LINE 6"-	FOOT	966	966					
	PAINT								
70300281	TEMPORARY PAVEMENT MARKING - LINE 24"-	FOOT	372	372					
	PAINT								
* 78000100	THERMOPLASTIC PAVEMENT MARKING -	SO FT	84	84					
	LETTERS AND SYMBOLS								
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE	FOOT	33433	33433					
	4"								
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE	FOOT	322	322					
	6"								

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL. ROUTE 173 (RIGHEIMER RD. TO OAK GROVE RD.)
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P.
RTE. 303

SECTION
FAP 0303 22 R52

COUNTY
MCHENRY

TOTAL
SHEETS 21

SHEET
NO. 3

FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT

CONTRACT NO. 62R96

* = SPECIALTY ITEMS

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

REVISED SHEET 2/21/2025

NON-PART 100% STATE