

MODEL: Default
FILE: \\atlantis-pw-bentley.com\atlantis-pw-01\Documents\Projects\10011101_CV_008011110_CAD\3_Sheets\01_General\016-7607-2r-500.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				80% FED 20% STATE
				BRIDGE
				0059 URBAN
28000510	INLET FILTERS	EACH	37	37
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	51	51
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	497	497
40600370	LONGITUDINAL JOINT SEALANT	FOOT	246	246
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	314	314
40604062	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	84	84
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	457	457
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	313	313
44000600	SIDEWALK REMOVAL	SQ FT	457	457
50102400	CONCRETE REMOVAL	CU YD	18.2	18.2
50157300	PROTECTIVE SHIELD	SQ YD	336	336
50300255	CONCRETE SUPERSTRUCTURE	CU YD	21.6	21.6
50300300	PROTECTIVE COAT	SQ YD	878	878
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3,070	3,070

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				80% FED 20% STATE
				BRIDGE
				0059 URBAN
50800515	BAR SPLICERS	EACH	48	48
52000110	PREFORMED JOINT STRIP SEAL	FOOT	136	136
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	11	11
52100520	ANCHOR BOLTS, 1"	EACH	22	22
59000200	EPOXY CRACK INJECTION	FOOT	90	90
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2
60260100	INLETS TO BE ADJUSTED	EACH	4	4
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	313	313
67100100	MOBILIZATION	L SUM	1	1
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	84	84
70300100	SHORT TERM PAVEMENT MARKING	FOOT	364	364
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	5,333	5,333
70300211	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS - PAINT	SQ FT	73	73
70300221	TEMPORARY PAVEMENT MARKING - LINE 4"- PAINT	FOOT	6,052	6,052
70300241	TEMPORARY PAVEMENT MARKING - LINE 6"- PAINT	FOOT	1280	1280
70300261	TEMPORARY PAVEMENT MARKING - LINE 12"- PAINT	FOOT	131	131

2

* - SPECIAL PROVISION
** - SPECIALTY ITEMS
*** - SPECIAL PROVISION & SPECIALTY ITEM



USER NAME = cpujari	DESIGNED - NKA	REVISED -
	DRAWN - NKA	REVISED -
PLOT SCALE = 100.0000" / in.	CHECKED - BA	REVISED +
PLOT DATE = 12/6/2024	DATE - 12/06/2024	REVISED +

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL ROUTE 171 OVER IHB RAILROAD
SUMMARY OF QUANTITIES

SCALE: NA SHEET 1 OF 3 SHEETS STA. TO STA.

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3565	FAU 3565 22 BI	COOK	59	3
CONTRACT NO. 62T50				
ILLINOIS FED. AID PROJECT				

REVISED SHEET 2/25/2025

REV-SEP