



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 22, 2025

SUBJECT FAP Route 750 (IL 185)
Project HBIP-F9K2(491)
Section (114)B-1
Fayette County
Contract No. 74327

Item No. 98, March 7th, 2025 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 10 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

STEEL PLATE BEAM GUARDRAIL SHORT RADIUS

This work consists of furnishing and erecting steel plate beam guardrail, type A and posts as shown in the plans and as directed by the Engineer. This work shall be performed as specified in Section 630 of the Standard Specifications and as detailed on the plans.

The guardrail shall be fabricated and constructed to the radius and length shown on the plans or as directed by the Engineer. The Contractor shall verify all dimensions and modifications in the field prior to ordering materials.

This work will be measured in feet along the top edge of the rail elements, continuous through laps and splices.

This work will be paid for at the contract unit price per FOOT for STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS).

TEMPORARY SLAB SUPPORT SYSTEM

Effective: July 27, 1994

Revised: January 21, 2025

Description: This item shall consist of furnishing all material, equipment, and labor necessary to support the slab as shown on the plans, as herein specified, and as directed by the Engineer.

Construction Requirements: The Contractor shall uniformly support the slab at the location(s) and minimum length(s) shown on the plans. The temporary slab support system shall be installed prior to removal of any portion of the existing bridge slab. After the support system is no longer required, it shall be completely removed. All materials shall become the property of the Contractor.

If the Contractor chooses to alter the slab support system shown on the plans, the Contractor shall submit the design and details of the support system that is proposed for approval of the Engineer prior to ordering of material and implementation. The Contractor shall submit calculations for the support system prepared and sealed by an Illinois Licensed Structural Engineer. Such approval shall in no way relieve the Contractor of responsibility for the safety of the structure. The supports used shall be such that vertical adjustments may be made in order to maintain the existing slab profile during the removal and replacement operation.

Basis of Payment: The work specified herein, as shown on the plans, and as directed by the Engineer, shall be paid for at the contract lump sum price for TEMPORARY SLAB SUPPORT SYSTEM.