

PLOT DRIVER = \$PLOTDRVL\$
PER TABLE = \$PENTBLL\$
FILE NAME = p:\w1\patk1cc-co-pw-bentley.com\patk1cc-co-pw-07\Documents\Chland_Park\2227\008\12_Design\12-3_CADD\SHEET\SL143\HD-sht-50Q.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FED / 20% LOCAL	80% FED / 20% LOCAL	80% FED / 20% LOCAL	100% LOCAL	100% LOCAL	80% FED / 20% LOCAL	100% LOCAL
				ROADWAY	EX. DRYLAND BRIDGE	TRAFFIC SIGNALS	LIGHTING	EVP	TRAINEES	UTILITY
				0004	0013	0021	0021	0021	0042	0043
				URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	5025	5025						
44000600	SIDEWALK REMOVAL	SQ FT	9672	9672						
44003100	MEDIAN REMOVAL	SQ FT	1888	1888						
44201347	CLASS C PATCHES, TYPE IV, 9 INCH	SQ YD	195	195						
44213200	SAW CUTS	FOOT	2513	2513						
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	131	131	1					
50102400	CONCRETE REMOVAL	CU YD	96	7		89				
50200100	STRUCTURE EXCAVATION	CU YD	8609	8609						
50300225	CONCRETE STRUCTURES	CU YD	514	497	17					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	2		2					
50300300	PROTECTIVE COAT	SQ YD	19		19					
50301350	CONCRETE SUPERSTRUCTURE (APPROACH SLAB)	CU YD	75		75					
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	22470	22470						
50800105	REINFORCEMENT BARS	POUND	25280	25280						
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	31750	470	31280					

* SPECIALITY ITEM



USER NAME = DT004	DESIGNED -	REVISED - 2/21/2025
	DRAWN -	REVISED -
PLOT SCALE = 20.0000 ' / in.	CHECKED -	REVISED -
PLOT DATE = 2/21/2025	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

JOHN HUMPHREY DRIVE AT 143RD STREET SUMMARY OF QUANTITIES			
SCALE:	SHEET 4	OF 18 SHEETS	STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2520	16-00078-00-CH	COOK	228	8
CONTRACT NO. 61K89				
ILLINOIS FED. AID PROJECT				

PLOT DRIVER = \$PLOTDRVL\$
PEN TABLE = \$PENITBL\$
FILE NAME = pwl\garlicco-pw-bentley.com\patrickco-pw-07\Documents\Oland Park\2227.005\12_Design\12.3_CADD\SHEET\$1\13\10D-shk-500.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FED / 20% LOCAL	80% FED / 20% LOCAL	80% FED / 20% LOCAL	100% LOCAL	100% LOCAL	80% FED / 20% LOCAL	100% LOCAL
				ROADWAY	EX. DRYLAND BRIDGE	TRAFFIC SIGNALS	LIGHTING	EVP	TRAINEES	UTILITY
				0004	0013	0021	0021	0021	0042	0043
				URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2						
60256910	MANHOLES TO BE ADJUSTED WITH NEW TYPE 20 FRAME AND GRATE	EACH	3	3						
60261510	INLETS TO BE ADJUSTED WITH NEW TYPE 20 FRAME AND GRATE	EACH	3	3						
* 60265700	VALVE VAULTS TO BE ADJUSTED	EACH	2							2
* 60266100	VALVE VAULTS TO BE RECONSTRUCTED	EACH	1							1
60500040	REMOVING MANHOLES	EACH	15	15						
60500050	REMOVING CATCH BASINS	EACH	6	6						
60500060	REMOVING INLETS	EACH	17	17						
60600605	CONCRETE CURB, TYPE B	FOOT	36	36						
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2118	2118						
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2665	2665						
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	3835	3835						
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	425	425	⚠					
63200312	GUARDRAIL REMOVAL	FOOT	337	337						
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2	⚠					
* 66900201	NON-SPECIAL WASTE DISPOSAL	CU YD	2170	2170						
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	⚠					

* SPECIALITY ITEM



USER NAME = DT004	DESIGNED -	REVISED - ⚠ 2/20/2025
	DRAWN -	REVISED -
PLOT SCALE = 20.0000 ' / in.	CHECKED -	REVISED -
PLOT DATE = 2/20/2025	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

JOHN HUMPHREY DRIVE AT 143RD STREET SUMMARY OF QUANTITIES			
SCALE:	SHEET 8	OF 18 SHEETS	STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2520	16-00078-00-CH	COOK	228	12
CONTRACT NO. 61K89				
ILLINOIS FED. AID PROJECT				