



NOTES

1. IN EVENT OF EXISTING INTERCONNECT CONDUIT CAN NOT BE MAINTENANCE. EXISTING FIBER OPTIC CABLE AND TRACER SHALL BE PULLED OUT OF EXISTING CONDUIT, STARTING AT THE EXISTING CONTROLLER BOX AT NW CORNER OF WILLOW AND SHERMER ROAD (HH-1) TO ALL THE WAY TO THE FIRST HANDHOLE NW CORNER OF THE BRIDGE (HH-3); HERE THE CABLES CAN BE STORED AND PROTECTED FOR REINSTALLATION (FOR WIRELESS INTERCONNECT OPTION). THIS WILL BE MEASURED AND PAID FOR AS "REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT", AND REPLACE CONDUIT BETWEEN HH-2 AND HH-3.
2. THERE ARE ADVANCE EMERGENCY VEHICLE PREEMPTION (EVP) IN BOTH DIRECTION OF WILLOW ROAD. ONE LOCATED ON WEST AND EAST SIDE OF THE VIADUCT SHALL BE MAINTENAN THOUGHT OUT THE DURATION OF THE PROJECT.
3. ANY HARDWARE OR ACCESSORIES REQUIRED TO SUPPORT TRAFFIC SIGNAL INTERCONNECT EXISTING CONDUIT OVER THE REBUILD OF THE CULVERT WILL NOT BE PAID FOR SEPARATELY.

FILE NAME : P:\2011\ME11007_Ver-Ver-PhI\CADD\W08.Willow_Rd\Shets\DI60W04-shl-TTS13-Interconn.dgn
 PLOT SCALE : 1/8"=50' / IN.
 USER NAME : Millennia Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148
 630.705.0110 voice, 630.839.2566 fax
 www.mps-ll.com
MILLENNIA PROFESSIONAL SERVICES

DESIGNED - TVN	REVISED -
DRAWN - MJW	REVISED -
CHECKED - TVN	REVISED -
DATE - 12/26/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WILLOW ROAD
EXISTING INTERCONNECT PLAN

SCALE: 1"=50' SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	1920.01-B-R	COOK	60	26
CONTRACT NO. 60W04				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				