

NOTES:

- 1. THE WIDTH OF THE FULL DEPTH PATCH OVER A TRENCH SHALL BE 12 (300) WIDER ON EACH SIDE OF THE TRENCH.
- 2. FOR METHOD OF MEASUREMENT AND BASIS OF PAYMENT, SEE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL".

SEQUENCE OF CONSTRUCTION (PATCHING FIRST)

- 1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.
- 2. REMOVE AND REPLACE WITH CLASS C OR D PATCH.
- 3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.

SEQUENCE OF CONSTRUCTION (MILLING FIRST)

- 1. MILL HMA FIRST IF THERE IS AT LEAST 41/2 INCHES OR MORE OF HMA MATERIAL ON TOP OF THE EXISTING PAVEMENT OR IF THE PAVEMENT IS FULL DEPTH HMA. A MINIMUM OF 2 INCHES OF HMA MATERIAL SHALL BE IN PLACE AFTER MILLING.
- 2. REMOVE AND REPLACE WITH FULL DEPTH CLASS D PATCHES TO TOP OF MILLED SURFACE.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

| F | ILE NAME = | USER NAME = bauerdl | DESIGNED - R. SHAH | REVISED - A. ABB | AS 04-27-98 | 8 | | PAVEMENT PATCHING FOR | | | SECTION | COUNTY | SHEETS | SHEET |
|---|-----------------------------------|-----------------------------|--------------------|-------------------|-------------|------------------------------|-----------------------|------------------------------|---------|------------------|------------|--------------------|--------|-------|
| | c:\projects\diststd22x34\bd22.dgn | | DRAWN - | REVISED - R. BORG | 01-01-07 | STATE OF ILLINOIS | | | | 330 | 2012-0861 | соок | 98 | 88 |
| | | PLOT SCALE = 50.000 ' / IN. | CHECKED - | REVISED - R. BOR | 0 09-04-07 | DEPARTMENT OF TRANSPORTATION | HMA SURFACED PAVEMENT | | | BD400-04 (BD-22) | | CONTRACT NO. 60W07 | | |
| | | PLOT DATE = 10/27/2008 | DATE - 10-25-94 | REVISED - K. ENG | 10-27-08 | | SCALE: NONE | SHEET NO. 1 OF 1 SHEETS STA. | TO STA. | FED. ROAD | ID PROJECT | | | |