INDEX OF SHEETS SHEET NO. DESCRIPTION **COVER SHEET** 2 TO 3 GENERAL NOTES AND STATE STANDARDS 4 TO 13 SUMMARY OF QUANTITIES 14 TO 23 TYPICAL SECTIONS 24 TO 32 SCHEDULE OF QUANTITIES 33 TO 34 ALIGNMENT AND BENCHMARKS PLAN AND PROFILE 35 TO 48 MAINTENANCE OF TRAFFIC GENERAL NOTES AND TYPICAL SECTIONS 52 TO 61 MAINTENANCE OF TRAFFIC 62 DETOUR PLAN 63 TO 65 EROSION CONTROL AND LANDSCAPING PLANS RR TO RO DRAINAGE AND UTILITIES 81 TO 83 INTERSECTION GRADING PLANS 84 SUPERELEVATION DETAILS 85 TO 100 PLAT OF HIGHWAYS 101 TO 103 PAVEMENT MARKING PLANS 104 TO 106 SIGNING PLANS 107 TO 122 PLANTING PLANS 123 TO 125 IRRIGATION PLANS 126 TO 128 TEMPORARY TRAFFIC SIGNAL -- BARRINGTON RD /SCHAUMBURG RD 129 TO 131 TRAFFIC SIGNAL MODERNIZATION - BARRINGTON RD /SCHAUMBURG RD 132 TO 133 TRAFFIC SIGNAL INSTALLATION - BARRINGTON RD /HOLMES WAY 134 TO 137 INTERCONNECT PLAN 138 MAST ARM MOUNTED STREET NAME SIGNS 139 TO 144 TRAFFIC SIGNAL DETAILS 145 TO 162 STREET LIGHTING PLANS AND DETAILS 163 TO 175 TEMPORARY LIGHTING PLANS AND DETAILS 176 TO 194 CONSTRUCTION DETAILS 195 TO 245 CROSS SECTIONS IDOT STANDARDS 000001-06 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS TEMPORARY EROSION CONTROL SYSTEMS PCC BASE COURSE WITH HMA BINDER & SURFACE COURSES 280001-07 353001-04 420001-07 PAVEMENT JOINTS PAVEMENT FABRIC 420701-02 424001-07 PERPENDICULAR CURB RAMPS FOR SIDEWALKS CORNER PARALLEL CURB RAMPS FOR SIDEWALKS 424011-01 424021-01 DEPRESSED CORNER FOR SIDEWALKS 442101-07 CLASS B PATCHES 442201-03 CLASS C AND D PATCHES CATCH BASIN TYPE A 602001-02 CATCH BASIN TYPE C 602011-02 602301-03 INLET - TYPE A 602306-03 INLET - TYPE B 602401-03 MANHOLE TYPE A 602601-02 PRECAST REINFORCED CONCRETE FLAT SLAB TOP 602701-02 MANHOLE STEPS 604001-03 FRAME AND LIDS TYPE 1 604036-02 GRATE TYPE 8 604051-03 FRAME AND GRATE TYPE 11 604056-03 FRAME AND GRATE TYPE 11V 604086-02 FRAME AND GRATE TYPE 23 604091-02 FRAME AND GRATE TYPE 24 606001-05 CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER OFF-RD OPERATIONS, MULTILANE, LESS THAN 15' TO EDGE OF PAVEMENT OFF-RD OPERATIONS, MULTILANE, LESS THAN 15' AWAY URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED 606301-04 701101-03 701106-02 701501-06 URBAN LANE CLOSURE, MULTILANE, 1W 2W WITH NONTRAVERSABLE MEDIAN 701601-08 701602-06 URBAN LANE CLOSURE, MULTILANE, 2W WITH BIDIRECTIONAL LEFT TURN LANE 701606-08 URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN URBAN LANE CLOSURE, MULTILANE INTERSECTION LANE CLOSURE MULTILANE, 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE 701701-08 701801-05 701901-02 TRAFFIC CONTROL DEVICES 720001-01 SIGN PANEL MOUNTING DETAILS 720006-03 SIGN PANEL ERECTION DETAILS 720016-03 MAST ARM MOUNTED STREET NAME SIGNS 728001-01 TELESCOPING STEEL SIGN SUPPORT TYPICAL PAVEMENT MARKINGS 780001-03 ELECTRICAL SERVICE INSTALLATION DETAILS 805001-01 814001-02 HANDHOLES 814006-02 DOUBLE HANDHOLES 857001-01 STANDARD PHASE DESIGNATION DIAGRAMS AND PHASE SEQUENCES 862001-01 UNINTERRUPTABLE POWER SUPPLY (UPS) 873001-02 TRAFFIC SIGNAL GROUNDING & BONDING 876001-02 PEDESTRIAN PUSH BUTTON POST STEEL MAST ARM ASSEMBLY AND POLE 16' THROUGH 55' STEEL MAST ARM ASSEMBLY AND POLE 56' THROUGH 75' 877001-05 877002-02 878001-09 CONCRETE FOUNDATION DETAILS SPAN WIRE MOUNTED SIGNALS AND FLASHING BEACON INSTALLATION 880001-01 TRAFFIC SIGNAL MOUNTING DETAILS 880006-01 886001-01 DETECTOR LOOP INSTALLATIONS SER NAME = d.k DESIGNED - JAT ..\2329\cad\sheet\2329_notes.dor DRAWN JAT

PLOT SCALE = 50.0000 '/ in.

PLOT DATE = 10/12/2012

CHECKED -

DATE

DJK

8-20-12

SPECIFICATIONS, STANDARDS AND SPECIAL PROVISIONS

- 1. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ("STANDARD SPECIFICATIONS"), ADOPTED JANUARY 1, 2012; THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS", ADOPTED JANUARY 1, 2013; THE LATEST EDITION OF THE "ILLINOIS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS", (IMUTCD); "THE STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS" JULY 2009 SIXTH EDITION, "AMERICAN STANDARDS FOR NURSERY STOCK, 2004 EDITION"; THE DETAILS IN THE PLANS, AND THE SPECIAL PROVISIONS AND IDOT STANDARD DRAWINGS INCLUDED IN THE CONTRACT DOCUMENTS.
- 2. NO WORK SHALL COMMENCE UNTIL TRAFFIC CONTROL REQUIREMENTS ARE MET.
- ALL UTILITY COMPANIES, SCHOOL DISTRICTS, AND LOCAL POLICE AND FIRE DEPARTMENTS SHALL BE NOTIFIED BY THE CONTRACTOR AT LEAST 72 HOURS PRIOR TO THE START OF CONSTRUCTION.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO ORDERING MATERIALS AND BEGINNING CONSTRUCTION.
- 5. WHEN REMOVING CURB AND GUTTER, PAYEMENT OR ANY OTHER STRUCTURE, THE CONTRACTOR SHALL TAKE EVERY PRECAUTION NECESSARY TO ENSURE THAT THERE WILL BE NO DAMAGE TO UNDERGROUND PUBLIC OR PRIVATE UTILITIES. UNDER NO CIRCUMSTANCES WILL THE USE OF A FROST BALL CONCRETE BREAKER BE ALLOWED.
- THE CONTRACTOR IS PROHIBITED FROM BURNING ANY MATERIAL WITHIN OR ADJACENT TO THE PROJECT LIMITS, ALL EXCESS OR WASTE MATERIAL SHALL BE EITHER HAULED AWAY FROM THE PROJECT SITE BY THE CONTRACTOR AND DEPOSITED AT LOCATIONS PROVIDED BY HIM, OR DISPOSED OF WITHIN THE RIGHT-OF-WAY IN A MANNER OTHER THAN BURNING, SUBJECT TO THE APPROVAL OF THE ENGINEER. NO EXTRA COMPENSATION WILL BE ALLOWED THE CONTRACTOR FOR ANY EXPENSE INCURRED BY COMPLYING WITH THE REQUIREMENTS OF THIS NOTE.

PAVING, SHOULDERS, CURB & GUTTER AND SIDEWALK

REVISED

REVISED

REVISED

REVISED

THE CONTRACTOR SHALL SAW CUT PAVEMENT, CURB & GUTTER, MEDIAN, SHOULDER, AND SIDEWALK AS INDICATED ON THE PLANS TO SEPARATE THE EXISTING MATERIAL TO BE REMOVED BY MEANS OF AN APPROVED CONCRETE SAW TO A DEPTH AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER. THIS WORK SHALL BE INCLUDED IN THE COST OF THE ITEM BEING REMOVED.

THE CONTRACTOR SHALL BE REQUIRED TO SAW VERTICAL CUTS SO AS TO FORM CLEAN VERTICAL JOINTS. SHOULD THE CONTRACTOR DEFACE ANY EDGE, A NEW SAWED JOINT SHALL BE PROVIDED AND ANY ADDITIONAL WORK, INCLUDING REMOVAL AND REPLACEMENT, SHALL BE DONE AT THE CONTRACTOR'S EXPENSE.

- 2. IT IS THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE THICKNESS OF THE EXISTING PAVEMENT AND WHETHER OR NOT IT CONTAINS REINFORCEMENT.
- HOT-MIX ASPHALT BINDER COURSE SHALL NOT BE PLACED ADJACENT TO CURB AND GUTTER UNTIL THE CURB AND GUTTER HAS BEEN PROPERLY CURED AND BACKFILLED TO THE SATISFACTION OF THE ENGINEER.
- 4. HOT-MIX ASPHALT SURFACE COURSE SHALL NOT BE PLACED UNTIL ALL EARTH EXCAVATION, TOPSOIL PLACEMENT, AND HOT-MIX ASPHALT BINDER COURSE HAVE BEEN COMPLETED TO THE SATISFACTION OF THE ENGINEER.
- 5. THE THICKNESSES OF HOT-MIX ASPHALT MIXTURES SHOWN ON THE PLANS ARE NOMINAL. DEVIATIONS MAY OCCUR DUE TO IRREGULARITIES IN THE SURFACE, BINDER, OR BASE UPON WHICH THE HOT-MIX ASPHALT MATERIALS ARE PLACED.
- 6. ALL CURB AND GUTTER CONSTRUCTED OVER A UTILITY TRENCH SHALL BE REINFORCED WITH
 TWO *4 REBARS FOR A LENGTH OF 20 FEET CENTERED OVER THE TRENCH. THIS WORK SHALL BE INCLUDED
 IN THE COST OF THE CURB AND GUTTER BEING CONSTRUCTED.
- 7. ALL SIDEWALK CONSTRUCTED OVER A UTILITY TRENCH SHALL BE REINFORCED WITH TWO *4 REBARS WHICH EXTEND 5 FEET BEYOND THE TRENCH WALLS. THIS WORK SHALL BE INCLUDED IN THE COST OF THE SIDEWALK BEING CONSTRUCTED.
- 8. ALL SAW CUTS AND DOWEL BARS REQUIRED FOR THE CONSTRUCTION OF CLASS B PATCHES SHALL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE COST OF "CLASS B PATCHES" OF THE TYPE AND THICKNESS REQUIRED.
- 9. FOR WORK OUTSIDE THE LIMITS OF BRIDGE APPROACH PAVEMENT, ALL REFERENCES IN THE HIGHWAY STANDARDS AND STANDARD SPECIFICATIONS FOR REINFORCEMENT, DOWEL BARS, AND TIE BARS IN PAVEMENT, SHOULDERS, CURB, GUTTER, COMBINATION CURB AND GUTTER, MEDIAN, AND CHAIR SUPPORTS FOR CRC PAVEMENT, SHALL BE EPOXY COATED, UNLESS NOTED ON THE PLAN.
- 10. THE MAXIMUM CROSS SLOPE AT ANY POINT IN THE TRAVERSABLE AREA OF THE SIDEWALK, INCLUDING THE AREAS THROUGH DRIVEWAYS, SHALL BE 2.00% ALL AREAS OF NEW SIDEWALK THAT EXCEED THIS MAXIMUM WILL BE REMOVED AND REPLACED AT THE CONTRACTOR'S EXPENSE.
- L. QUANTITIES FOR CLASS B PATCHES (SCHAUMBURG ROAD) AND CLASS D PATCHES (BARRINGTON ROAD AND HOLMES WAY) HAVE BEEN INCLUDED FOR USE IN REPAIRING THE EXISTING PAVEMENT WHEN DIRECTED BY THE ENGINEER.
- 12. EXISTING BACKER ROD AND JOINT SEALANT WITHIN EXISTING CRACKS AND JOINTS SHALL BE REMOVED WHEN DIRECTED BY THE ENGINEER. THIS WORK SHALL BE INCLUDED IN THE COST OF "JOINT OR CRACK FILLING" OR "MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS".

TREE REMOVAL, CLEARING AND HEDGE REMOVAL

- 1. THE CONTRACTOR'S ATTENTION IS CALLED TO THE FACT THAT THE PRESERVATION OF EXISTING TREES IS OF THE UTMOST IMPORTANCE TO THE VILLAGE. ALL TREE PROTECTION, TREE REMOVAL, TREE PRUNING AND ROOT PRUNING SHALL BE COMPLETED BEFORE CONSTRUCTION OPERATIONS COMMENCE IN ANY AREA. AT NO TIME SHALL THE CONTRACTOR PRUNE OR REMOVE ANY TREES UNLESS SPECIFICALLY DIRECTED BY THE ENGINEER.
- 2. TEMPORARY FENCE SHALL BE ERECTED ALONG THE DRIP LINE OF EXISTING TREES TO REMAIN WHEN DIRECTED BY THE ENGINEER. AFTER TREES ARE SAFELY FENCED NOTHING IS TO BE STORED, DRIVEN, OR DISTURBED INSIDE THE FENCE. REMOVE PROTECTIVE TEMPORARY FENCE ONLY AFTER ALL CONSTRUCTION WORK HAS BEEN COMPLETED.

ROADWAY EXCAVATION

- 1. AGGREGATE SUBGRADE IMPROVEMENT HAS BEEN INCLUDED IN THE CONTRACT TO REPLACE SOILS WHICH TEND TO BE UNSTABLE WHEN WET. THE ACTUAL NEED FOR REMOVAL AND REPLACEMENT WITH AGGREGATE SUBGRADE IMPROVEMENT WILL BE DETERMINED IN THE FIELD AT THE TIME OF CONSTRUCTION BY THE ENGINEER. IF UNSUITABLE SOILS ARE ENCOUNTERED THE SOILS SHALL BE REMOVED AND REPLACED WITH AGGREGATE SUBGRADE IMPROVEMENT. THESE LIMITS MAY BE ALTERED BY THE ENGINEER IF FIELD CONDITIONS SO WARRANT. REMOVAL OF THESE UNSUITABLE SOILS SHALL BE PAID FOR AS "REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL."
- THE QUANTITIES OF FURNISHED EXCAVATION HAVE BEEN CALCULATED ASSUMING THAT ALL MATERIAL EXCAVATED UNDER THE PAY ITEM EARTH EXCAVATION WILL BE REMOVED FROM THE JOB SITE. IF THE CONTRACTOR EXCAVATES SUITABLE MATERIAL AND PLACES IT IN AREAS OF THE PROJECT REQUIRING EMBANKMENT UNDER THE PAY ITEM EARTH EXCAVATION, AS DESCRIBED IN SECTION 202 OF THE STANDARD SPECIFICATIONS AND AS APPROVED BY THE ENGINEER, THE APPLICABLE DEDUCTION TO THE FURNISHED EXCAVATION QUANTITY SHALL BE MADE AS DEFINED BY ARTICLE 204.07(B), EXCEPT THAT A SHRINKAGE FACTOR OF 15% SHALL BE USED. THE CONTRACTOR SHALL NOT BE ALLOWED A CHANGE IN THE UNIT PRICES FOR EARTH EXCAVATION OR FURNISHED EXCAVATION BASED ON THESE CHANGES TO THE QUANTITIES. THE VOLUMES OF FURNISHED EXCAVATION SHOWN ON THE PLANS ARE THE COMPACTED VOLUMES. THE VOLUMES SHOWN ON THE PLANS HAVE NOT BEEN ADJUSTED TO ACCOUNT FOR SHRINKAGE DUE TO COMPACTION.

UTILITIES

- THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES. THE LOCATION OF PUBLIC OR PRIVATE UTILITIES SHOWN ON THE PLANS ARE APPROXIMATE AND THE ENGINEER DOES NOT GUARANTEE THEIR ACCURACY.
- COORDINATION OF ANY UTILITY WORK INVOLVED IN THE CONSTRUCTION AREA WILL BE DISCUSSED AT THE PRECONSTRUCTION CONFERENCE,
- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 1-800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, GAS, WATER, SEWER AND CABLE TELEVISION FACILITIES. (48 HOURS NOTIFICATION IS REQUIRED.)
- 4. WHENEVER DURING CONSTRUCTION OPERATIONS ANY LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF DRAINAGE STRUCTURES SUCH THAT THE NATURAL FLOW OF WATER IS OBSTRUCTED, IT SHALL BE REMOVED AT THE CLOSE OF EACH WORKING DAY. AT THE CONCLUSION OF CONSTRUCTION OPERATIONS, ALL UTILITY STRUCTURES SHALL BE FREE FROM DIRT AND DEBRIS. THE COST OF ALL MATERIALS REQUIRED AND ALL LABOR NECESSARY TO COMPLY WITH THE ABOVE PROVISIONS WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED AS INCLUDED IN THE COST OF THE STORM SEWERS AND DRAINAGE STRUCTURES INSTALLED AS PART OF THIS PROJECT.
- 5. ANY EXISTING OR PROPOSED SEWER DAMAGED BY THE CONTRACTOR DURING CONSTRUCTION SHALL BE REPLACED BY THE CONTRACTOR TO THE SATISFACTION OF THE ENGINEER AT NO COST TO THE VILLAGE,
- THE CONTRACTOR SHALL RECEIVE NO ADDITIONAL COMPENSATION FOR CONSTRUCTION STAGING NECESSARY TO ACCOMMODATE UTILITY RELOCATION OR ADJUSTMENT AND/OR FOR DELAYS CAUSED BY UTILITY RELOCATION OR ADJUSTMENT.
- 7. THE CONTRACTOR SHALL FURNISH ALL LABOR, EQUIPMENT AND MATERIAL NECESSARY FOR DEWATERING TRENCH EXCAVATIONS AS WELL AS SHORING TRENCH WALLS DURING UTILITY OPERATIONS. THE COST TO COMPLY WITH THE ABOVE SHALL BE INCLUDED IN THE COST OF THE STORM SEWERS AND DRAINAGE STRUCTURES INSTALLED AS PART OF THIS PROJECT.

DISTRICT ONE STANDARDS

BE-305	LIGHT POLE FOUNDATION, METAL
BD~310	LIGHT POLE FOUNDATION OFFSET 40' TO 47 1/2' M.H., 15" BOLT CIRCLE
BE-800	TEMPORARY LIGHT POLE DETAILS
BD-8	DETAILS FOR FRAMES AND LIDS ADJUSTMENT WITH MILLING
BD-32	BUTT JOINT AND HMA TAPER DETAILS
TC-10	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND
	DRIVEWAYS
TC-11	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW
	RESISTANT)
TC-13	DISTRICT ONE TYPICAL PAVEMENT MARKINGS
TC-14	TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC)
TC-16	PAVEMENT MARKING LETTERS AND SYMBOLS FOR TRAFFIC STAGING
TC-21	DETOUR SIGNING FOR CLOSING STATE HIGHWAYS
TC-22	ARTERIAL ROAD INFORMATION SIGN
TC-26	DRIVEWAY ENTRANCE SIGNING

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

| COUNTY | SHEET NO. 1 OF 2 SHEETS | FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID | PROJECT N-CMM-5003/05/5/1